

SECTION 096516 - RESILIENT SHEET FLOORING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Vinyl sheet floor covering, without backing.
- 2. Rubber sheet floor covering, without backing.

B. Related Sections:

- 1. Division 09 Section "Resilient Base and Accessories" for resilient base, reducer strips, and other accessories installed with resilient floor coverings.

1.3 SUBMITTALS

- A. Product Data: For each type of product indicated.

- B. LEED Submittals: Follow submittal requirements of Division 01 Section "Submittal Requirements" and provide product data on the LEED Materials Documentation Cover Sheet attached as an Appendix to Division 01 Section "Sustainable Design and LEED Requirements."

- C. Shop Drawings: For each type of floor covering. Include floor covering layouts, locations of seams, edges, columns, doorways, enclosing partitions, built-in furniture, cabinets, and cutouts.

- 1. Show details of special patterns.

- D. Samples for Initial Selection: For each type of floor covering indicated.

- E. Seam Samples: For seamless-installation technique indicated and for each floor covering product, color, and pattern required; with seam running lengthwise and in center of 6-by-9-inch Sample applied to a rigid backing and prepared by Installer for this Project.

- F. Product Schedule: For floor coverings. Use same designations indicated on Drawings.

- G. Maintenance Data: For each type of floor covering to include in maintenance manuals.

1.4 QUALITY ASSURANCE

- A. Installer Qualifications: A qualified installer who employs workers for this Project who are competent in techniques required by manufacturer for floor covering installation indicated.
 - 1. Engage an installer who employs workers for this Project who are trained or certified by floor covering manufacturer for installation techniques required.
- B. Fire-Test-Response Characteristics: As determined by testing identical products according to ASTM E 648 or NFPA 253 by a qualified testing agency.
 - 1. Critical Radiant Flux Classification: Class I, not less than 0.45 W/sq. cm.
- C. Mockups: Build mockup of seam to demonstrate aesthetic effects and set quality standards for materials and execution.
 - 1. Size: Minimum 10 linear feet.
 - 2. Mockup may remain as part of completed work.
- D. Preinstallation Conference: Conduct conference at Project site.
 - 1. At least 7 days prior to starting installation of flooring, conduct a meeting to review detailed requirements for materials and to determine procedures for a satisfactory installation of flooring materials.
 - 2. Review methods and procedures related to curing and protection of concrete substrate.
 - 3. Review and finalize construction schedule and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Store floor coverings and installation materials in dry spaces protected from the weather, with ambient temperatures maintained within range recommended by manufacturer, but not less than 50 deg F or more than 90 deg F. Store rolls upright.

1.6 PROJECT CONDITIONS

- A. Maintain ambient temperatures within range recommended by manufacturer, but not less than 70 deg F or more than 85 deg F, in spaces to receive floor coverings during the following time periods:
 - 1. 48 hours before installation.
 - 2. During installation.
 - 3. 48 hours after installation.
- B. Until Substantial Completion, maintain ambient temperatures within range recommended by manufacturer, but not less than 55 deg F or more than 95 deg F.
- C. Close spaces to traffic during floor covering installation.
- D. Close spaces to traffic for 48 hours after floor covering installation.

PEARL PLACE 2

- E. Install floor coverings after other finishing operations, including painting, have been completed.

1.7 EXTRA MATERIALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Floor Covering: Furnish quantity not less than 10 linear feet for every 500 linear feet or fraction thereof, in roll form and in full roll width for each color, pattern, and type of floor covering installed.

PART 2 - PRODUCTS

2.1 MATERIALS, GENERAL

- A. Meet requirements of LEED for Homes Mid-Rise 2010 Credit MR 2.2 as defined in Division 01 Section "Sustainable Design and LEED Requirements" for this type of material.

2.2 VINYL SHEET FLOOR COVERING (SV-1)

- A. Products: Subject to compliance with requirements, provide the following:
 - 1. Armstrong; Adobe.
- B. Vinyl Sheet Floor Covering with Backing: ASTM F 1303.
 - 1. Type (Binder Content): Type I, minimum binder content of 90 percent.
 - 2. Wear-Layer Thickness: Grade 1.
 - 3. Overall Thickness: As standard with manufacturer.
 - 4. Backing Class: Class B (nonfoamed plastic).
- C. Wearing Surface: Smooth.
- D. Sheet Width: 12 feet.
- E. Seaming Method: Chemical welded, with flash cove base at Type A Units.
- F. Colors and Patterns: Sanjani Slate No. 80817 Topaz .

2.3 VINYL SHEET FLOOR COVERING (SV-2)

- A. Products: Subject to compliance with requirements, provide the following:
 - 1. Armstrong; Adobe.
- B. Vinyl Sheet Floor Covering with Backing: ASTM F 1303.

PEARL PLACE 2

1. Type (Binder Content): Type I, minimum binder content of 90 percent.
2. Wear-Layer Thickness: Grade 1.
3. Overall Thickness: As standard with manufacturer.
4. Backing Class: Class B (nonfoamed plastic).

C. Wearing Surface: Smooth.

D. Sheet Width: 12 feet.

E. Seaming Method: Chemical welded.

F. Colors and Patterns: Echo Lake No. 18011 Khaki.

2.4 VINYL SHEET FLOOR COVERING (SV-2 Alternate)

A. Products: Subject to compliance with requirements, provide the following:

1. Mannington Mills, Inc.; Magna.

B. Vinyl Sheet Floor Covering with Backing: ASTM F 1303.

1. Type (Binder Content): Type II, minimum binder content of 34 percent.
2. Wear-Layer Thickness: Grade 1.
3. Overall Thickness: .080 inch.
4. Interlayer Material: None.
5. Backing Class: Class A (fibrous).

C. Wearing Surface: Smooth.

D. Sheet Width: 6 feet.

E. Seaming Method: Heat welded with flash cove base.

F. Colors and Patterns: No. 18016 Crystal Rosa.

2.5 RUBBER SHEET FLOOR COVERING (SV-3)

A. Products: Subject to compliance with requirements, provide the following:

1. Altro; Timbersafe II.

B. Unbacked Rubber Sheet Floor Covering: ASTM F 1859.

1. Type: Type I (homogeneous rubber sheet).
2. Thickness: As standard with manufacturer.

C. Hardness: Manufacturer's standard hardness, measured using Shore, Type A durometer per ASTM D 2240.

D. Wearing Surface: Textured.

PEARL PLACE 2

- E. Sheet Width: 6'-7".
- F. Colors and Patterns: As selected by Architect from full range of industry colors.

2.6 INSTALLATION MATERIALS

- A. Trowelable Leveling and Patching Compounds: Latex-modified, portland cement based or blended hydraulic-cement-based formulation provided or approved by manufacturer for applications indicated.
- B. Adhesives: Water-resistant type recommended by manufacturer to suit floor covering and substrate conditions indicated.
 - 1. Use adhesives that have a VOC content of not more than 50 g/L when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- C. Seamless-Installation Accessories:
 - 1. Heat-Welding Bead: Manufacturer's solid-strand product for heat welding seams.
 - a. Color: Match floor covering.
 - 2. Chemical-Bonding Compound: Manufacturer's product for chemically bonding seams.
 - a. VOC Content: Not more than 510 g/L. when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- D. Integral-Flash-Cove-Base Accessories:
 - 1. Cove Strip: 1-inch radius provided or approved by manufacturer.
 - 2. Cap Strip: Tapered vinyl cap provided or approved by manufacturer.
 - 3. Corners: Metal inside and outside corners and end stops provided or approved by manufacturer.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, with Installer present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.
- B. Verify that finishes of substrates comply with tolerances and other requirements specified in other Sections and that substrates are free of cracks, ridges, depressions, scale, and foreign deposits that might interfere with adhesion of floor coverings.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Prepare substrates according to manufacturer's written instructions to ensure adhesion of floor coverings.
- B. Concrete Substrates: Prepare according to ASTM F 710.
 - 1. Verify that substrates are dry and free of curing compounds, sealers, and hardeners.
 - 2. Remove substrate coatings and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, using mechanical methods recommended by manufacturer. Do not use solvents.
- C. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound and remove bumps and ridges to produce a uniform and smooth substrate.
- D. Do not install floor coverings until they are same temperature as space where they are to be installed.
 - 1. Move floor coverings and installation materials into spaces where they will be installed at least 48 hours in advance of installation.
- E. Sweep and vacuum clean substrates to be covered by floor coverings immediately before installation.

3.3 SUBSTRATE TESTING

- A. General: Review testing reports for concrete slabs provided by the General Contractor or flooring contractor may conduct own tests as approved by the manufacturer of the flooring material.

3.4 FLOOR COVERING INSTALLATION

- A. Comply with manufacturer's written instructions for installing floor coverings.
- B. Unroll floor coverings and allow them to stabilize before cutting and fitting.
- C. Lay out floor coverings as follows:
 - 1. Maintain uniformity of floor covering direction.
 - 2. Minimize number of seams; place seams in inconspicuous and low-traffic areas, at least 6 inches away from parallel joints in floor covering substrates.
 - 3. Match edges of floor coverings for color shading at seams.
 - 4. Avoid cross seams.
- D. Scribe and cut floor coverings to butt neatly and tightly to vertical surfaces, permanent fixtures, and built-in furniture including cabinets, pipes, outlets, and door frames.
- E. Extend floor coverings into toe spaces, door reveals, closets, and similar openings.

- F. Maintain reference markers, holes, or openings that are in place or marked for future cutting by repeating on floor coverings as marked on substrates. Use chalk or other nonpermanent marking device.
- G. Install floor coverings on covers for telephone and electrical ducts and similar items in installation areas. Maintain overall continuity of color and pattern between pieces of floor coverings installed on covers and adjoining floor covering. Tightly adhere floor covering edges to substrates that abut covers and to cover perimeters.
- H. Adhere floor coverings to substrates using a full spread of adhesive applied to substrate to produce a completed installation without open cracks, voids, raising and puckering at joints, telegraphing of adhesive spreader marks, and other surface imperfections.
- I. Seamless Installation:
 - 1. Heat-Welded Seams: Comply with ASTM F 1516. Rout joints and use welding bead to permanently fuse sections into a seamless floor covering. Prepare, weld, and finish seams to produce surfaces flush with adjoining floor covering surfaces.
 - 2. Chemically-Bonded Seams: Bond seams with chemical-bonding compound to permanently fuse sections into a seamless floor covering. Prepare seams and apply compound to produce tightly-fitted seams without gaps, overlays, or excess bonding compound on floor covering surfaces.
- J. Integral-Flash-Cove Base: Cove floor coverings 6 inches up vertical surfaces. Support floor coverings at horizontal and vertical junction by cove strip. Butt at top against cap strip.
 - 1. Install metal corners at inside and outside corners.

3.5 CLEANING AND PROTECTION

- A. Comply with manufacturer's written instructions for cleaning and protection of floor coverings.
- B. Perform the following operations immediately after completing floor covering installation:
 - 1. Remove adhesive and other blemishes from floor covering surfaces.
 - 2. Sweep and vacuum floor coverings thoroughly.
 - 3. Damp-mop floor coverings to remove marks and soil.
- C. Protect floor coverings from mars, marks, indentations, and other damage from construction operations and placement of equipment and fixtures during remainder of construction period.

END OF SECTION 096516