

SECTION 124813 - ENTRANCE FLOOR MATS AND FRAMES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:

- 1. Carpet-type mats.

1.3 SUBMITTALS

- A. Product Data: Include manufacturer's specifications and installation instructions, construction details, material descriptions, dimensions of individual components and profiles, and finishes for each type of floor mat.
- B. Samples for Selection: For each type of floor mat and frame indicated.
- C. Maintenance Data: For cleaning and maintaining floor mats to include in maintenance manuals.

1.4 QUALITY ASSURANCE

- A. Source Limitations: Obtain floor mats and frames through one source from a single manufacturer.
- B. Accessibility Requirements: In addition to requirements of authorities having jurisdiction, provide installed floor mats that comply with Section 4.5 in the U.S. Architectural & Transportation Barriers Compliance Board's "Americans with Disabilities Act (ADA), Accessibility Guidelines for Buildings and Facilities (ADAAG)."

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - 1. Carpet-Type Mats:

## PEARL PLACE 2

- a. Mats Incorporated.

### 2.2 FLOOR MATS

- A. General: Provide colors, patterns, and profiles of materials, including metals and metal finishes indicated or specified. If not indicated, provide colors, patterns, and profiles selected by Architect from manufacturer's standards.
- B. Carpet-Type Mats: Polypropylene carpet tile bonded to 1/8- to 1/4-inch- thick, flexible vinyl backing to form mats 3/8 or 7/16 inch thick with nonraveling edges.
  1. Available Products: Products that may be incorporated into the Work include, but are not limited to, the following:
    - a. Supreme Nop by Mats, Inc.

### 2.3 FABRICATION

- A. General: Where possible, verify sizes by field measurement before shop fabrication.
- B. Floor Mats: Shop fabricate units to greatest extent possible in sizes as indicated. If not otherwise indicated, provide single unit for each mat installation; do not exceed manufacturer's recommended maximum sizes for units that are removed for maintenance and cleaning. Where joints in mats are necessary, space symmetrically and away from normal traffic lanes. Miter corner joints in framing elements with hairline joints or provide prefabricated corner units without joints.

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Install surface-type units to comply with manufacturer's written instructions at locations indicated; coordinate with entrance locations and traffic patterns.

### 3.2 PROTECTION

- A. Defer installation of floor mats until Project is near Substantial Completion.

END OF SECTION 124813