

SECTION 32 28 50- SITE IMPROVEMENTS

PART 1 - GENERAL

1.01 GENERAL PROVISIONS

- A. The CONDITIONS OF THE CONTRACT and all Sections of Division 1 are hereby made a part of this Section.

1.02 DESCRIPTION OF WORK

- A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, and without limiting the generality thereof furnish and install the following:
 - 1. Site Signage
 - 2. Bicycle Rack

PART 2 - PRODUCTS & EXECUTION

2.01 BASIC MATERIALS:

- A. Reinforcement: ASTM A 615, Grade 60, deformed, hot-dipped galvanized.
 - 1. Provide minimum reinforcement ration of 3 percent.
- B. Galvanizing: Hot-dipped galvanized after fabrication, conforming to:
 - 1. ASTM A 386 for assembled products.
 - 2. ASTM A 153 for iron and steel hardware.

2.02 BASIC INSTALLATION REQUIREMENTS:

- A. Install all materials and equipment in compliance with manufacturer's recommendations, and as indicated on Drawings.

2.03 Site Signage

- A. Provide parking signs as indicated on the plans.
 - 1. Conform to MDOT and ADA Standards for all site signage.

2.06 Bicycle Racks

- A. Bicycle rack to be Dero Bike Rack, Model # BW2H-IG, as manufactured by Dero Bike Rack Co., Minneapolis, MN, or approved equal.
- B. Bicycle Hitch to be Dero Bike Rack, Model # BIKE HITCH, as manufactured by Dero Bike Rack Co., Minneapolis, MN, or approved equal.

END OF SECTION 32 28 50