



- FLOOR FRAMING NOTES:**
1. See structural notes sheet S1.
  2. Provide (2) 1/2" x 9/2" LVL w/ 2" rigid insulation header at all exterior window and door openings unless noted otherwise.
  3. Window headers shall be spaced together w/ 3 rows of 16d nails @ 12" o.c.
  4. Provide double joists below all upper parallel walls.
  5. Provide solid blocking at mid-span of all joists.
  6. See architectural drawings and field verify all dimensions and openings.
  7. Add solid blocking between floor joists below all posts.
  - 8.

**3rd FLOOR FRAMING PLAN**

Scale: 1/4" = 1'-0"

- FLOOR FRAMING NOTES:**
1. See structural notes sheet S1.
  2. Provide (2) 1/2" x 9/2" LVL w/ 2" rigid insulation header at all exterior window and door openings unless noted otherwise.
  3. Window headers shall be spaced together w/ 3 rows of 16d nails @ 12" o.c.
  4. Provide double joists below all upper parallel walls.
  5. Provide solid blocking at mid-span of all joists.
  6. See architectural drawings and field verify all dimensions and openings.
  7. Add solid blocking between floor joists below all posts.
  - 8.

**2nd FLOOR FRAMING PLAN**

Scale: 1/4" = 1'-0"