



Submittal Data Sheet

FTXS09LVJU

FTXS09LVJU





Submittal Data Sheet

FTXS09LVJU

FTXS09LVJU

PERFORMANCE

Indoor Unit Model No.	FTXS09LVJU	Indoor Unit Name:	FTXS09LVJU
Type:	Wall Mounted	Rated Cooling Conditions:	Indoor (°F DB/WB): 80 / 67 Ambient (°F DB/WB): 95 / 75
Rated Cooling Capacity (Btu/hr):	9,000	Rated Heating Conditions:	Indoor (°F DB/WB): 70 / 70 Ambient (°F DB/WB): 47 / 43
Sensible Capacity (Btu/hr):	8,100	Rated Piping Length(ft):	
Cooling Input Power (kW):	0.590	Rated Height Separation (ft):	
Rated Heating Capacity (Btu/hr):	12,000		
Heating Input Power (kW):	0.79		

INDOOR UNIT DETAILS

Power Supply (V/Hz/Ph):	208-230 / 60 / 1	Airflow Rate (H/M/L/SL) (CFM):	381/279/194/145
Power Supply Connections:	See Outdoor Unit for Electrical Specs	Moisture Removal (Gal/hr):	2.4
Min. Circuit Amps MCA (A):		Gas Pipe Connection (inch):	3/8
Max Overcurrent Protection (MOP) (A):		Liquid Pipe Connection (inch):	1/4
Dimensions (HxWxD) (in):	11-5/8 x 31-1/2 x 8-7/16	Condensate Connection (inch):	5/8
Panel (HxWxD) (in):		Sound Pressure (H/M) (dBA):	41/22
Net Weight (lb):	20	Sound Power Level (dBA):	
Panel Weight (lb):		Ext. Static Pressure (Rated/Max) (inWg):	0.00 / 0.00

Submittal Data Sheet

FTXS09LVJU

FTXS09LVJU

DIMENSIONAL DRAWING

FTXS09,12LVJU

