



Submittal Data Sheet

FTXS15LVJU

FTXS15LVJU

FEATURES

- Intelligent eye occupancy sensor
- Weekly timer for programmable comfort
- Low ambient heat operation down to 0° F
- Titanium apatite photocatalytic air purifying
- 12 year limited parts and compressor warranty with online registration

BENEFITS

- Quiet operation





Submittal Data Sheet

FTXS15LVJU

FTXS15LVJU

PERFORMANCE

Indoor Unit Model No.	FTXS15LVJU	Indoor Unit Name:	FTXS15LVJU
Type:	Wall Mounted	Rated Cooling Conditions:	Indoor (°F DB/WB): 80 / 67 Ambient (°F DB/WB): 95 / 75
Rated Cooling Capacity (Btu/hr):	15,000	Rated Heating Conditions:	Indoor (°F DB/WB): 70 / 70 Ambient (°F DB/WB): 47 / 43
Sensible Capacity (Btu/hr):		Rated Piping Length(ft):	
Cooling Input Power (kW):	0.040	Rated Height Separation (ft):	
Rated Heating Capacity (Btu/hr):	18,000		
Heating Input Power (kW):	0.04		

INDOOR UNIT DETAILS

Power Supply (V/Hz/Ph):	208-230 / 60 / 1	Airflow Rate (H/M/L/SL) (CFM):	568/385/360/360
Power Supply Connections:	L1, L2, Ground	Moisture Removal (Gal/hr):	0.8
Min. Circuit Amps MCA (A):		Gas Pipe Connection (inch):	1/2
Max Overcurrent Protection (MOP) (A):		Liquid Pipe Connection (inch):	1/4
Dimensions (HxWxD) (in):	13 x 45-11/16 x 16-7/8	Condensate Connection (inch):	5/8
Panel (HxWxD) (in):		Sound Pressure (H/M/L/SL) (dBA):	45/32/32/32
Net Weight (lb):	31	Sound Power Level (dBA):	61
Panel Weight (lb):		Ext. Static Pressure (Rated/Max) (inWg):	0.00 / 0.00

Submittal Data Sheet

FTXS15LVJU

FTXS15LVJU

DIMENSIONAL DRAWING

FTXS15,18_LVJU

