



## Submittal Data Sheet

FTXS18LVJU

FTXS18LVJU

### FEATURES

- Intelligent eye occupancy sensor
- Weekly timer for programmable comfort
- Low ambient heat operation down to 0° F
- Titanium apatite photocatalytic air purifying
- 12 year limited parts and compressor warranty with online registration

### BENEFITS

- Quiet operation





## Submittal Data Sheet

FTXS18LVJU

FTXS18LVJU

### PERFORMANCE

Indoor Unit Model No.	FTXS18LVJU	Indoor Unit Name:	FTXS18LVJU
Type:	Wall Mounted	Rated Cooling Conditions:	Indoor (°F DB/WB): 80 / 67 Ambient (°F DB/WB): 95 / 75
Rated Cooling Capacity (Btu/hr):	18,000	Rated Heating Conditions:	Indoor (°F DB/WB): 70 / 70 Ambient (°F DB/WB): 47 / 43
Sensible Capacity (Btu/hr):		Rated Piping Length(ft):	
Cooling Input Power (kW):	0.040	Rated Height Separation (ft):	
Rated Heating Capacity (Btu/hr):	21,600		
Heating Input Power (kW):	0.04		

### INDOOR UNIT DETAILS

Power Supply (V/Hz/Ph):	208-230 / 60 / 1	Airflow Rate (H/M/L/SL) (CFM):	583/385/360/360
Power Supply Connections:	L1, L2, Ground	Moisture Removal (Gal/hr):	1.0
Min. Circuit Amps MCA (A):		Gas Pipe Connection (inch):	1/2
Max Overcurrent Protection (MOP) (A):		Liquid Pipe Connection (inch):	1/4
Dimensions (HxWxD) (in):	13 x 45-11/16 x 16-7/8	Condensate Connection (inch):	5/8
Panel (HxWxD) (in):		Sound Pressure (H/M/L/SL) (dBA):	46/33/33/33
Net Weight (lb):	31	Sound Power Level (dBA):	62
Panel Weight (lb):		Ext. Static Pressure (Rated/Max) (inWg):	0.00 / 0.00

**Submittal Data Sheet**

FTXS18LVJU

FTXS18LVJU

**DIMENSIONAL DRAWING**

**FTXS15,18\_LVJU**

