

SECTION 085216

PLASTIC CLAD WOOD WINDOWS

PART 1 - GENERAL

1.1 SUMMARY

- A. This Section includes the following vinyl-clad wood-framed window product types:
1. Awning windows.

1.2 SUBMITTALS

- A. Product Data: Include construction details, material descriptions, fabrication methods, dimensions of individual components and profiles, hardware, finishes, and operating instructions for each type of wood window indicated.
- B. Shop Drawings: Include plans, elevations, sections, details, hardware, attachments to other Work, operational clearances, and the following:
1. Mullion details, including reinforcement and stiffeners.
 2. Joinery details.
 3. Expansion provisions.
 4. Flashing and drainage details.
 5. Weather-stripping details.
 6. Thermal-break details.
 7. Glazing details.
 8. Window cleaning provisions.
- C. Samples for Selection: Submit color samples with factory-applied color finishes.
- D. Product Test Reports: Based on evaluation of comprehensive tests performed within the last four years by a qualified testing agency, for each type, grade, and size of wood window. Test results based on use of down-sized test units will not be accepted.
- E. Maintenance Data: For operable window sash, operating hardware, weather stripping, and finishes to include in maintenance manuals.

1.3 QUALITY ASSURANCE

- A. Installer Qualifications: An installer acceptable to wood window manufacturer for installation of units required for this Project.
- B. Testing Agency Qualifications: An independent testing agency, acceptable to authorities having jurisdiction, with the experience and capability to conduct the testing indicated, as documented according to ASTM E 548.
- C. Source Limitations: Obtain wood windows through one source from a single manufacturer.

- D. Product Options: Drawings indicate size, profiles, and dimensional requirements of wood windows and are based on the specific system indicated. Refer to Division 1 Section "Product Requirements."
 - 1. Do not modify intended aesthetic effects, as judged solely by Architect, except with Architect's approval. If modifications are proposed, submit comprehensive explanatory data to Architect for review.
- E. Fenestration Standard: Comply with AAMA/WDMA 101/I.S.2, "Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors," for minimum standards of performance, materials, components, accessories, and fabrication unless more stringent requirements are indicated.
 - 1. Provide WDMA-certified wood windows with an attached label.
- F. Glazing Publications: Comply with published recommendations of glass manufacturers and GANA's "Glazing Manual" unless more stringent requirements are indicated.

1.4 PROJECT CONDITIONS

- A. Field Measurements: Verify wood window openings by field measurements before fabrication and indicate measurements on Shop Drawings.
 - 1. Established Dimensions: Where field measurements cannot be made without delaying the Work, establish opening dimensions and proceed with fabricating wood windows without field measurements. Coordinate wall construction to ensure that actual opening dimensions correspond to established dimensions.

1.5 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace wood windows that fail in materials or workmanship within specified warranty period. Failures include, but are not limited to, the following:
 - 1. Failure to meet performance requirements.
 - 2. Structural failures including excessive deflection.
 - 3. Water leakage, air infiltration, or condensation.
 - 4. Faulty operation of movable sash and hardware.
 - 5. Deterioration of metals, metal finishes, and other materials beyond normal weathering.
 - 6. Insulating glass failure.
- B. Warranty Period: 10 years from date of Substantial Completion.
- C. Warranty Period for Glass: 20 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Vinyl-Clad Wood Windows:

- a. Andersen Commercial Group; Andersen Corp.; 400 Series.

2.2 MATERIALS, GENERAL

- A. Wood: Clear ponderosa pine or another suitable fine-grained lumber; kiln-dried to a moisture content of 6 to 12 percent at time of fabrication; free of visible finger joints, blue stain, knots, pitch pockets, and surface checks larger than 1/32 inch (0.8 mm) deep by 2 inches (51 mm) wide; water-repellent preservative treated.
- B. Vinyl for Cladding: Consisting of a rigid PVC sheath, made from PVC complying with ASTM D 4726, not less than 35-mil (0.9-mm) average thickness, in permanent, integral color, white and sandtone finish, mechanically bonded to exterior wood sash and frame members.
 1. Provide white color for Existing Barn and Sandtone for Addition.
- C. Wood Trim and Glazing Stops: Material and finish to match frame members.
- D. Clad Trim and Glazing Stops: Hollow extrusions or Clad-wood material; material and finish to match clad frame members.
- E. Fasteners: Aluminum, nonmagnetic stainless steel, epoxy adhesive, or other materials warranted by manufacturer to be noncorrosive and compatible with wood window members, cladding, trim, hardware, anchors, and other components.
 1. Exposed Fasteners: Unless unavoidable for applying hardware, do not use exposed fasteners. For application of hardware, use fasteners that match finish of member or hardware being fastened, as appropriate.
- F. Anchors, Clips, and Accessories: Aluminum, nonmagnetic stainless steel, or zinc-coated steel or iron complying with ASTM B 633 for SC 3 severe service conditions; provide sufficient strength to withstand design pressure indicated.
- G. Reinforcing Members: Aluminum, nonmagnetic stainless steel, nickel/chrome-plated steel complying with ASTM B 456 for Type SC 3 severe service conditions, or zinc-coated steel or iron complying with ASTM B 633 for SC 3 severe service conditions; provide sufficient strength to withstand design pressure indicated.
- H. Compression-Type Weather Stripping: Provide compressible weather stripping designed for permanently resilient sealing under bumper or wiper action, and completely concealed when wood window is closed.
 1. Weather-Stripping Material: Manufacturer's standard system and materials complying with AAMA/WDMA 101/I.S.2.
- I. Sliding-Type Weather Stripping: Provide woven-pile weather stripping of wool, polypropylene, or nylon pile and resin-impregnated backing fabric. Comply with AAMA 701/702.
 1. Weather Seals: Provide weather stripping with integral barrier fin or fins of semirigid, polypropylene sheet or polypropylene-coated material.

2.3 GLAZING

- A. Glass: Manufacturer's standard factory-glazing system of Clear, insulating-glass with low-e coating or film, argon-gas filled units. Tempered where required by Code.

2.4 HARDWARE

- A. General: Provide manufacturer's standard hardware fabricated from aluminum, stainless steel, carbon steel complying with AAMA 907, or other corrosion-resistant material compatible with wood[and aluminum cladding]; designed to smoothly operate, tightly close, and securely lock wood windows and sized to accommodate sash or ventilator weight and dimensions. Do not use aluminum in frictional contact with other metals. Where exposed, provide die-cast zinc with special coating finish.
- B. Counterbalancing Mechanism: Comply with AAMA 902.
 - 1. Sash-Balance Type: Concealed spring-loaded, block-and-tackle type of size and capacity to hold sash stationary at any open position.
- C. Handles: Applied sash lift on bottom rail of forward placed operating sash; one per sash.
 - 1. Provide Contemporary Sash Lift in white finish.
- D. Locks and Latches: Designed to allow unobstructed movement of the sash across adjacent sash in direction indicated and operated from the inside only.
- E. Gear-Type Rotary Operators: Comply with AAMA 901 when tested according to ASTM E 405, Method A.
 - 1. Operation Function: All ventilators move simultaneously and securely close at both jambs without using additional manually controlled locking devices.
 - 2. Provide Classic Series hardware in white finish.
- F. Four- or Six-Bar Friction Hinges: Comply with AAMA 904.
 - 1. Locking mechanism and handles for manual operation.
 - 2. Friction Shoes: Provide friction shoes of nylon or other nonabrasive, nonstaining, noncorrosive, durable material.

2.5 INSECT SCREENS

- A. General: Design windows and hardware to accommodate screens in a tight-fitting, removable arrangement, with a minimum of exposed fasteners and latches. Locate screens on inside of awning windows and outside of double-hung windows of window and provide for each operable exterior sash or ventilator.
- B. Aluminum Insect Screen Frames: Manufacturer's standard aluminum alloy complying with SMA 1004. Fabricate frames with mitered or coped joints, concealed fasteners, and removable PVC spline/anchor concealing edge of frame.
 - 1. Aluminum Tubular Framing Sections and Cross Braces: Roll-formed from aluminum sheet with minimum wall thickness as required for class indicated.
 - 2. Finish: Baked-on organic coating in color selected by Architect from manufacturer's full range.
- C. Glass-Fiber Mesh Fabric: 18-by-14 (1.4-by-1.8-mm) or 18-by-16 (1.4-by-1.6-mm) mesh of PVC-coated, glass-fiber threads; woven and fused to form a fabric mesh resistant to corrosion,

shrinkage, stretch, impact damage, and weather deterioration in the following color. Comply with ASTM D 3656.

1. Mesh Color: Charcoal gray.

2.6 ACCESSORIES

- A. Simulated Divided Lites: 7/8 inches wide with internal spacer, extruded aluminum exterior bar and wood interior bar. Bars adhered to glass with double coated foam tape.
- B. Electric Operators: Provide factory-installed, Andersen Awning Electric Operators for the clerestory windows indicated on the drawings.

2.7 FABRICATION

- A. General: Fabricate wood windows, in sizes indicated, that comply with AAMA/WDMA 101/I.S.2 for performance class and performance grade indicated. Include a complete system for assembling components and anchoring windows.
 1. Provide windows sizes of standard available sizes without fabricating custom sizes, unless indicated otherwise. Provide windows with dimensions of not less than 2 inches smaller than indicated on the drawings or provide next size larger.
- B. General: Fabricate wood windows, in sizes indicated, that comply with requirements and that meet or exceed AAMA/WDMA 101/I.S.2 performance requirements for the following window type. Include a complete system for assembling components and anchoring windows.
- C. Fabricate wood windows that are reglazable without dismantling sash or ventilator framing.
- D. Weather Stripping: Provide full-perimeter weather stripping for each operable sash and ventilator, unless otherwise indicated.
 1. Double-Hung Windows: Provide weather stripping only at horizontal rails of operable sash.
- E. Factory machine windows for openings and hardware that is not surface applied.
- F. Mullions: Provide mullions and cover plates as shown, matching window units, complete with anchors for support to structure and installation of window units. Allow for erection tolerances and provide for movement of window units due to thermal expansion and building deflections, as indicated. Provide mullions and cover plates capable of withstanding design loads of window units.
- G. Factory-Glazed Fabrication: Except for light sizes in excess of 100 united inches (2500 mm width plus length), glaze wood windows in the factory where practical and possible for applications indicated. Comply with requirements in Division 8 Section "Glazing" and with AAMA/WDMA 101/I.S.2.
- H. Glazing Stops: Provide nailed or snap-on glazing stops coordinated with Division 8 Section "Glazing" and glazing system indicated. Provide glazing stops to match sash and ventilator frames.

- I. Complete fabrication, assembly, finishing, hardware application, and other work in the factory to greatest extent possible. Disassemble components only as necessary for shipment and installation. Allow for scribing, trimming, and fitting at Project site.

2.8 WOOD FINISHES

- A. Factory-Finished Windows: Provide fabricator's standard factory finish consisting of prime coat and two finish coats; 3-mil (0.76-mm) dry film thickness. Apply finish to exposed exterior and interior wood surfaces.
 1. Color: White at both the Addition and the Existing Barn.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine openings, substrates, structural support, anchorage, and conditions, with Installer present, for compliance with requirements for installation tolerances; rough opening dimensions; levelness of sill plate; coordination with wall flashings, vapor retarders, and other built-in components; and other conditions affecting performance of work.
 1. Masonry Surfaces: Visibly dry and free of excess mortar, sand, and other construction debris.
 2. Wood Frame Walls: Dry, clean, sound, well nailed, free of voids, and without offsets at joints. Ensure that nail heads are driven flush with surfaces in opening and within 3 inches (76 mm) of opening.
 3. Metal Surfaces: Dry; clean; free of grease, oil, dirt, rust, corrosion, and welding slag; without sharp edges or offsets at joints.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. General: Comply with manufacturer's written instructions for installing windows, hardware, accessories, and other components; Drawings; and Shop Drawings.
- B. Install windows level, plumb, square, true to line, without distortion or impeding thermal movement, anchored securely in place to structural support, and in proper relation to wall flashing and other adjacent construction.
- C. Set sill members in bed of sealant or with gaskets, as indicated, for weathertight construction.
- D. Metal Protection: Separate aluminum and other corrodible surfaces from sources of corrosion or electrolytic action at points of contact with other materials by complying with requirements specified in "Dissimilar Materials" Paragraph in Appendix B in AAMA/WDMA 101/I.S.2.

3.3 ADJUSTING

- A. Adjust operating sashes and ventilators, screens, hardware, and accessories for a tight fit at contact points and weather stripping for smooth operation and weathertight closure. Lubricate hardware and moving parts.

3.4 PROTECTION AND CLEANING

- A. Protect window surfaces from contact with contaminating substances resulting from construction operations. In addition, monitor window surfaces adjacent to and below exterior concrete and masonry surfaces during construction for presence of dirt, scum, alkaline deposits, stains, or other contaminants. If contaminating substances do contact window surfaces, remove contaminants immediately according to manufacturer's written recommendations.
- B. Clean exposed surfaces immediately after installing windows. Avoid damaging protective coatings and finishes. Remove excess sealants, glazing materials, dirt, and other substances.
- C. Clean factory-glazed glass immediately after installing windows. Comply with manufacturer's written recommendations for final cleaning and maintenance. Remove nonpermanent labels and clean surfaces.
- D. Remove and replace glass that has been broken, chipped, cracked, abraded, or damaged during construction period.

END OF SECTION