Space horizontal boards equally along height of screen.

5" +/-

Existing steel posts to remain. Remove aluminum horizontals, angle bracket mounts, and vertical aluminum slats complete.

Attach 1x composite wood nailer to front face of each post with galvanized cariage bolts

Install 1x6 composite wood horizontal boards w/ +/- 3/4" gaps between boards.

8 1/2"

DESIGN INTENT IS TO UTILIZE COMPOSITE TRIM SIMILAR TO AZEK IN A A LIGHT TAN COLOR SIMILAR TO THE COLOR OF THE EXISTING METAL SIDING.

DETAIL A @ MECHANICAL SCREEN

Scale: 1" = 1'-0"

WINTON SCOTT ARCHITECTS, PA
5 Milk Street
Portland, Maine   04101
207 774 4811

**POWER PAY
OFFICE FIT-UP**

ASK 50
DECEMBER 18, 2009