GENERAL DEMOLITION NOTES:

THESE NOTES SHALL APPLY TO ALL DEMO PLANS FOR THIS BUILDING.

1. WIRING FOR EXISTING FIRE ALARM DEVICES TO BE REMOVED & NOT INTENDED TO BE REUSED SHALL BE REMOVED ENTIRELY. DO NOT ABANDON FIRE ALARM WIRING ABOVE CEILINGS OR IN WIREWAYS.
2. MAINTAIN, OR RESTORE IF INTERRUPTED BY REMOVALS OR IN PATH OF NEW CONSTRUCTION, ALL CONDUITS AND CONDUCTORS PASSING THROUGH AND SERVING UNDISTURBED AREAS (SHOWN OR NOT SHOWN).
3. ALL EXISTING CONDUITS STUBBED THROUGH FLOOR SERVING ITEMS TO BE REMOVED (SHOWN OR NOT SHOWN) AND NOT REQUIRED TO BE REUSED SHALL BE CUT OFF FLUSH WITH THE SLAB LEVEL AND SEALED.
4. IN ANY AREA REQUIRING THE PERFORMANCE OF ANY TRADES WORK, THIS CONTRACTOR SHALL CAREFULLY REMOVE AND STORE ANY ELECTRICAL ITEMS IN THE PATH OF WORK, REINSTALLING AND RECONNECTING SAME AS REQUIRED IN ACCORDANCE WITH THE PLANS AND/OR AS DIRECTED AFTER COMPLETION OF OTHER TRADES WORK IN THAT AREA.
5. INVENTORY ITEMS WITH SALVAGE VALUE THAT ARE REMOVED, AND PROVIDE A LIST TO THE OWNER FOR THEIR SELECTION OF ITEMS TO BE RETAINED. ALL ITEMS REJECTED BY THE OWNER SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE REMOVED FROM THE SITE.
6. WHERE EXISTING DEVICE IS NOTED TO BE REMOVED, RECESSED JUNCTION BOX MAY BE ABANDONED IN PLACE. PROVIDE BLANK PLATE AT BOX AND PAINT TO MATCH ADJACENT SURFACES.

Reviewed for Code Compliance
Inspection Division
Approved with Conditions
Date: 07/29/15

KEY PLAN

LEGEND:

E	EXISTING TO REMAIN
ER	EXISTING RELOCATED
NR	NEW TO REPLACE EXISTING IN EXISTING LOCATION
R	EXISTING TO BE REMOVED
RR	REMOVE & RELOCATE EXISTING
	FIRE ALARM HORN / LIGHT
	MULTI-CANDLA STROBE
	MULTI-CANDELA SPEAKER/STROBE
	CEILING MOUNTED MULTI-CANDELA SPEAKER/STROBE
	FIRE ALARM SYSTEM CEILING MOUNTED HEAT DETECTOR - "EL" FOR ELEVATOR SHUNT TRIP
	FIRE ALARM SYSTEM CEILING MOUNTED SMOKE DETECTOR - "EL" FOR ELEVATOR RECALL
	WALL MOUNTED FIRE ALARM SYSTEM MANUAL PULL STATION
	KNOX BOX
	JUNCTION BOX
	DOOR HOLD-OPEN DEVICE CONNECTION
	FIRE ALARM SYSTEM/SPRINKLER SYSTEM PRESSURE SWITCH
	FIRE ALARM SYSTEM/SPRINKLER SYSTEM FLOW SWITCH
	FIRE ALARM SYSTEM/SPRINKLER SYSTEM TAMPER SWITCH
	FIRE ALARM SYSTEM DUCT MOUNTED SMOKE DETECTOR
FACP	FIRE ALARM SYSTEM CONTROL PANEL
FAA	FIRE ALARM ANNUNCIATOR
	GAS SHUT-OFF
EX RT	RADIO TRANSMITTER BOX
MM	MONITOR MODULE
RT	TEST STATION
RM	RELAY MODULE
	ANSUL GAS TANK
AMP	FIRE ALARM AMPLIFIER

REV.	DESCRIPTION	DATE
--	--	--
--	--	--
--	--	--
0	ISSUED FOR BID	06.12.15

ISSUED FOR BID
06.12.15
CURRENT ISSUE STATUS:

STATE OF MAINE
STEPHANIE J. LAPLANT
No. 10272
LICENSED PROFESSIONAL ENGINEER
06.12.15

WBRC
ARCHITECTS• ENGINEERS
WWW.WBRCAE.COM
BANGOR, MAINE 207-947-4511
PORTLAND, MAINE 207-828-4511
SARASOTA, FLORIDA 941-556-0757

PORTLAND HIGH SCHOOL
FIRE ALARM UPGRADES
PROJECT: PORTLAND, ME

BASEMENT FIRE ALARM REMOVALS PLAN
SHEET TITLE:

WBRC CAD FILE:	404100 – FD100
PROJECT No.	404100
SCALE:	AS NOTED
PROJECT MANAGER:	SJL
DRAWN BY:	KRM
CHECKED BY:	SJL
GRAPHIC SCALE:	0" 1"
SHEET No.	FD100

© COPYRIGHT 2015 WBRC

A7	BASEMENT FIRE ALARM REMOVALS PLAN
1/8" = 1'-0"	--

6/16/2015 2:43 PM I:\4001-4100\404100 PORTLAND HIGH SCHOOL FIRE ALARM SYSTEM\2 DESIGN\DWGS\BLDG\PORTLAND SCHOOL EXISTING DRAWINGS\SHEETS\404100-FD100 BASEMENT FIRE ALARM REMOVALS PLAN.DWG KYLE.MAHAR