



RESIDENTIAL BUILDING - 200 SQ. FT. PER OCCUPANT
 BUILDING TYPICAL FLOOR AREA - 9470 SQ. FT.
 200 - 47.35
 48 OCCUPANTS PER FLOOR
 RESIDENTIAL EGRESS CAPACITY
 STAIRWAY WIDTH - 0.3' PER PERSON
 0.3' x 48' - 14.4' MIN WIDTH REQUIRED
 DOOR TO STAIRWAYS = 34' CLEAR

MASONRY WALLS
 STAIRCASE AND
 THICK CEMENT
 PLASTER ON MTL
 LATHING

1 TYPICAL FLOOR PLAN
 SCALE: 1/4"=1'

A-7	REMEDIAL WORK TO STAIRCASE 1 & 2	Date 7/31/06	Scale 1/4" = 1'-0"	Project: THE METROPOLITAN 439 CONGRESS ST 439 CONGRESS ST PORTLAND, ME	ARCHETYPE, P.A. ARCHITECTS 48 Union Wharf Portland, Maine 04101 (207) 772-6022 Fax (207) 772-4056	OWNER: METROPOLITAN APARTMENTS, LLC C/O PORT PROPERTY MANAGEMENT 104 GRANT STREET PORTLAND, ME 04101
	Revisions:					