



Southgate Steeplejacks

Steeple Building • Steeple Restoration

279 Websterville Road • Barre, Vermont 05641 • (802) 839-6099
www.southgatesteeplejacks.com

PHASE 3 ON SITE

OK, so now the new 8 new primed Belfry exterior walls are ready to ship, the completed Lantern/Spire is ready to ship, the Balustrade is ready to ship, all the structural repairs have been made to the steeple on site. The repaired Belfry Dome is covered in Ice/Watershield, and the hole where the Lantern sits is capped. Now it is time to ship the belfry down. We will build a scaffolding tower in the side yard that will allow us to completely assemble and finish paint the belfry faces on the ground, under cover, into a single unit. Once the Belfry is assembled we will bring down the Lantern/Spire. Now, its crane time.

Using the crane, we will detach the roof of the Enclosure to the ground. Then, we will fly up and slip the Belfry onto the frame. Then we will fly up and attach the Lantern/Spire, then the Vane. Now we will send the crane home.

So, what was a Wood Protective Scaffolding Enclosure is now simply wood scaffolding. Working from this scaffolding, we will install new copper roofing onto the Belfry Dome. We will install the Urns on new steel posts. I urge you not to paint all the new copper roofing. We will re-connect the lightning protection. We will do the final punchlist inspection. We will take down our Scaffolding. We will install the Balustrade. We will clean up, de-rig, and be gone.