

Portland, Maine



Yes. Life's good here.

Danielle P. West-Chuhta
Corporation Counsel

Michael I. Goldman
Associate Counsel

Anne M. Torregrossa
Associate Counsel

Victoria E. Morales
Associate Counsel

November 4, 2016

NOTICE OF INTENT TO PROSECUTE

To Whom it May Concern,

Please see the attached Notice of Violation and Order to Correct from the City of Portland Fire Prevention Bureau. The Fire Prevention Bureau has referred this matter to me for prosecution in the event that you do not complete and return the required plan of action by the date contained in the Notice of Violation. Your failure to comply will result in the issuance of a summons for you to appear in court, and the imposition of civil penalties in the minimum amount of \$100 per violation per day.

Please contact the Fire Prevention Bureau at (207)874-8400 to resolve these outstanding violations. I look forward to your anticipated cooperation and appreciate your efforts to help keep the citizens of Portland safe.

Sincerely,

A handwritten signature in blue ink that reads 'Anne M. Torregrossa'. The signature is written in a cursive, flowing style.

Anne M. Torregrossa
Associate Corporation Counsel
City of Portland

CITY OF PORTLAND
 FIRE PREVENTION BUREAU
 380 Congress Street, Portland, Maine 04101
 fireprevention@portlandmaine.gov
 (207) 874-8400

NOTICE OF VIOLATION AND ORDER TO CORRECT

November 4, 2016

Location 21 CHESTNUT ST	CBL 027 C010	Inspection Date 10/25/2016
Inspector Sean Donaghue	Inspection Type FP Routine Inspection	Status Failed

The City of Portland Fire Department inspected this property, and found the fire and life safety code violations listed below, which you are hereby ordered to correct. You must complete the proposed date of completion column by proposing a reasonable timeframe to remedy each violation. This form must be received by the Fire Prevention Bureau no later than 11/30/2016. The Bureau reserves the right to reject or modify any proposed plan of action, and may require evidence of sufficient financial and technical capacity to complete the proposed plan. Please contact the Bureau with any questions.

YOUR FAILURE TO SUBMIT A PLAN OF ACTION BY THE DATE PROVIDED, OR TO CORRECT ANY VIOLATION WITHIN THE APPLICABLE TIME FRAME, MAY RESULT IN LEGAL ACTION AGAINST YOU, THE IMPOSITION OF CIVIL PENALTIES, AND THE PURSUIT OF OTHER LEGAL REMEDIES.

Violation	Proposed Date of Completion
<p>NFPA 101-7.9.3 EMERGENCY LIGHTS REQUIRE MAINTENANCE; 7.9.3 Periodic Testing of Emergency Equipment 7.9.3.1 Required emergency lighting systems shall be tested in accordance with one of the three options offered by 7.9.3.1.1, 7.9.3.1.2, or 7.9.3.1.3. 7.9.3.1.1 Testing of required emergency lighting systems shall be permitted to be conducted as follows: (1) Functional testing shall be conducted monthly with a minimum of 3 weeks and a maximum of 5 weeks between tests, for not less than 30 seconds, except as otherwise permitted by 7.9.3.1.1(2). (2) The test interval shall be permitted to be extended beyond 30 days with the approval of the authority having jurisdiction. (3) Functional testing shall be conducted annually for a minimum 1-1/2 hours if the emergency lighting system is battery powered. (4) The emergency lighting equipment shall be fully operational for the duration of the test required by 7.9.3.1.1(1) and (3). (5) Written records of visual inspections and tests shall be kept by the owner for inspection by the authority having jurisdiction.</p> <p>East stairwell 8th floor and basement by Storage B, 6th floor by 604 emergency lights don't illuminate when tested, maintenance required</p>	<p>___/___/___</p>
<p>NFPA 101- 9.7.4.1 FIRE EXTINGUISHERS REQ- OTHER; Where required by the provisions of another section of this code, portable fire extinguishers shall be installed, inspected, and maintained in accordance with NFPA 10, Standard for Portable Fire Extinguishers.</p> <p>Basement, across from elevator, has marking and hook for fire extinguisher, but no fire extinguisher present. Please replace missing fire extinguisher.</p>	<p>___/___/___</p>

Violation	Proposed Date of Completion
<p>NFPA 101-7.9.3 EMERGENCY LIGHTS REQUIRE MAINTENANCE; 7.9.3 Periodic Testing of Emergency Equipment 7.9.3.1 Required emergency lighting systems shall be tested in accordance with one of the three options offered by 7.9.3.1.1, 7.9.3.1.2, or 7.9.3.1.3. 7.9.3.1.1 Testing of required emergency lighting systems shall be permitted to be conducted as follows: (1) Functional testing shall be conducted monthly with a minimum of 3 weeks and a maximum of 5 weeks between tests, for not less than 30 seconds, except as otherwise permitted by 7.9.3.1.1(2). (2) The test interval shall be permitted to be extended beyond 30 days with the approval of the authority having jurisdiction. (3) Functional testing shall be conducted annually for a minimum 1-1/2 hours if the emergency lighting system is battery powered. (4) The emergency lighting equipment shall be fully operational for the duration of the test required by 7.9.3.1.1(1) and (3). (5) Written records of visual inspections and tests shall be kept by the owner for inspection by the authority having jurisdiction.</p> <p>Peace Food Market: Emergency lights behind coffee area don't illuminate when tested, please fix.</p>	<p>___/___/___</p>
<p>NFPA 1 EXCESSIVE/DISORDERLY STORAGE; Reference NFPA 1 for excessive fuel-load.</p> <p>Peace Food Market: No storage permitted 36" in front of electrical panel or 30" on either side, panel located near bathroom.</p>	<p>___/___/___</p>
<p>NFPA 70- 590.6 EXTENSION CORDS; Ground-fault protection for personnel for all temporary wiring installations shall be provided to comply with 590.6(A) and (B). This section shall apply only to temporary wiring installations used to supply temporary power to equipment used by personnel during construction, remodeling, maintenance, repair, or demolition of buildings, structures, equipment, or similar activities.</p> <p>Peace Food Market: No permanent use of extension cords permitted, usage noted for freezer by bathroom, for microwave in the coffee area, and on the side wall near floor in the rear of main counter.</p>	<p>___/___/___</p>
<p>NFPA 70 MISSING BOX COVERS; Refer to NFPA 70, National Electrical Code, on standards for missing box covers.</p> <p>Peace Food Market: Side wall near floor in the rear of the main counter box requires mounting and cover.</p>	<p>___/___/___</p>

VIOLATOR CERTIFICATION

I agree to remedy the violations listed within the timeframes provided. If I require additional time to comply, I understand that I must contact the Fire Prevention Bureau prior to the deadline to request an extension, which is entirely within the Bureau’s discretion to grant or deny.

I further understand that it is my responsibility to schedule a reinspection of my property once the violations have been remedied to do so. My failure to schedule a reinspection shall be deemed an admission that the violations have not been remedied.

If I fail to comply with this agreement, I understand that I am liable for penalties pursuant to the City of Portland Code of Ordinances §§ 1-15 and 10-25, and 30-A M.R.S. § 4452 and may be subject to further legal action.

Date

Responsible Party

Date

Responsible Party

SEEN AND AGREED

Date

Fire Prevention Bureau