



Exterior Masonry Work Notes

- ① Repair and rebuild brickwork as necessary. Replace missing, broken or deteriorated units with bricks that match the size, color, texture and flash of the original bricks. Match original coursing, joint width and adjacent mortar color. Use ASTM C-270 proportion specification Type O Cement-Lime mortar with sand that is graded to match the original sand in color, texture and particle size distribution.
- ② Repair and rebuild Portland CT brownstone as necessary. Hone or re-tool units in good structural condition where possible to re-establish appropriate surface appearance. Patch units in fair condition with Jahn M-70 to re-establish original profiles and surface appearance. Cast and replace missing units or units in poor condition with Jahn M-150 to re-establish original profiles and surface appearance. All work undertaken using Jahn shall follow the manufacturer's specifications for material handling, application and finishing. All repaired and replaced brownstone units shall match the original size, shape, profile, color and texture of the original brownstone units in good condition. Where there is no representative stone remaining with an original profile intact, a compatible design will be submitted for review and approval to the SHPO prior to casting and installation. Maintain original joint width and locations in the rebuilt work unless otherwise approved by the SHPO.

NOTE: See Numbers keyed on elevations for specific areas requiring repairs.

R. Dean Bingham, AIA
Architect
 55 Roberts Street
 Portland, Maine 04102
 (207) 774-7779

Grace
Chestnut Street Church
 Chestnut Street
 Portland, ME

Title
 South and East Elevations

Scale: 1/8" = 1'-0"

Date: 6/09/08

Revisions

Sheet
A4