Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 09/23/16

REMOVE CONCRETE SIDEWALK PAVING AT AREA SHOWN - CUT ALONG EXISTING CONTROL JOINTS. OWNER WILL REMOVE EXISTING SPILL BUCKET STRUCTURE, INSTALL NEW STRUCTURE, AND REPLACE BASE FILL.

COMPACT BASE MATERIAL AND INSTALL NEW CONCRETE SIDEWALK PAVING AFTER CITY WORK IS COMPLETE. COORDINATE WORK WITH CITY.

Sidewalk Repair Plan

1/8"=1'-0"

0 4 8 16

NORTH

Portland City Hall
Myrtle Street Entrance Renovations
Portland, Maine

Myrtle St. SIdewalk Repair Plan

WINTON SCOTT ARCHITECTS
5 Milk Street
Portland, Maine 04101

Scale: As Shown

A 2

July 26, 2016