

Marhsall Austin Map 24 Specifications

FEATURES

WATER RESISTANT AND FIRE RETARDANT CANOPY, BACKDROP, SIDEWALLS, AND SKIRTING

Keep your performers safe and dry with a canopy that covers the entire main floor plus an additional foot front and rear.

EQUIPMENT COMPARTMENTS / SPLASH GUARDS

Have all the items you need (adapters, bulbs and more) under secure lock and key. 6.25 cubic feet of welded, .120 thick polished aluminum tread plate, full-length stainless steel hinge and tee handle turn locks.

ELECTRICAL DISTRIBUTION

The stage is equipped with a 125-amp 220/110v load center with eight independent circuits. A 50-amp twist lock is also included.

LEVELING AND STABILIZER JACKS

A patented feature of the stage, the 7,000 lb. capacity jacks are drop leg and crank adjustable, allowing you to level the stage on uneven surfaces.

A COMPLETE TOWING PACKAGE

Including a 7,000 lb, capacity tandem axle with electric brakes (all wheels), a two inch 5,000 capacity ball-type coupler, two 10,000 pound capacity safety chains, breakaway brakes, reflectors, brake lights and more. All stages comply with DOT and NHTSA requirements.

STAGE EXTENSIONS

Lightweight and sturdy 4' X 4' extensions attach to stage frame or each other for maximum stability. Two aluminum fold-up legs permit fine and coarse adjustments for easy set up.

WINCH ASSEMBLE

The winch is manual and does not require outside or on-board power to raise the roof. The patented single-winch mechanism allows the canopy to rise to a ten-degree slope (front to back) and helps shed water and maintain the great looking slope roof design.

BANNER PACKAGE

Maximize your advertising and revenue stream by selling sponsorship space on the stage or by leveraging your own brand to it's fullest. The Banner Package features a special aluminum attachment that affixes to the stage to support a 32 ft x 4 ft Valance Banner and two 4 ft x 12.5 ft vertical side banners. Marshall Austin can place your graphics, size them appropriately and output your banners for any sponsor or event.

ROLLING BILLBOARD PACKAGE

Take your brand on the road with the Rolling Billboard Package to promote your city, your company, your events or your sponsors. We reproduce your artwork



into large, durable, custom decals that are affixed to interchangeable aluminum side panels. You can easily switch the panels to feature different signage as your advertising needs change. It's more that just your stage – it's your rolling billboard.

MOVIE-IN-THE-PARK-PACKAGE

Convert the Marshall Austin Mobile Stage into an outdoor theater with the Movie-in-The-Park Package – the only adaptable stage conversion on the market. The Movie-in-The-Park Package includes a large venue projector and a 24 ft. x 13.5 ft movie screen. The movie screen easily mounts to the front of the stage. And with our remote screen controller, you are ready to go in minutes!



TOWING DIMENSIONS

Overall length: (including hitch 28 ft. 7 in.)
Stage length: 24 ft.
Stage width: 8 ft. 5.5 in.
Overall height: 9 ft. 5.5 in.

PERFORMANCE DIMENSIONS

Stage floor: 24 ft. X 16 ft.
Stage height (from ground): 44 in.

MAXIMUM FRONT CANOPY

Height from floor: 12 ft. 6 in.

MAXIMUM REAR CANOPY

Height from floor: 9 ft. 6 in.

WEIGHT

Gross vehicle weight: 4,240 lbs.
Hitch tongue load (empty): 350 lbs.

ALLOWABLE LOADS

Stage floor load: 100 psf

TENT TOP LOADING

Single side loaded: 1640 lbs.
Both sides loaded: 2800 lbs.

WIND SPEED

Maximum wind speed: 50-60 mph
Maximum uplift on roof: 13 psf