

Apex3224 Specifications

Trailer:

Trailer Length	34'
Trailer Width	102"
Trailer Height	12' 2"
Cargo Space	6' 11" x 31' 4"
Cargo Capacity	5,000 lbs
Trailer Weight	14,150 lbs
Tongue Weight	1,800 lbs
Rear Axle Rating	10,000 lbs
Front Axle Rating	10,000 lbs
GVWR	20,000 lbs

Stage Roof:

Covered Roof	26' 3" x 34'
Deck to Roof Top	17' 8"
Deck to Bottom of Ctr I-Beam	15' 8"
Deck to Bottom of Upstage I-Beam	15' 11"
Deck to Bottom of Downstage I-Beam	15' 5"
Surface	Fiberglass / Alum
Roof Lifting Capability	4,500 lbs
Fly Bays	2,000 lbs ea
Downstage I-Beam	1,000 lbs even dist
Upstage I-Beam	1,000 lbs even dist
Center I-Beams	1,000 lbs even dist ea
Total Roof Capacity	8,000 lbs
Slide Out Bar Length	2' 3"



Stage Deck:

Floor Size	32' x 23' 8"
Floor Height	46" to 66"
Ground to Roof	23' 1"
Floor Rating	150 lb/sqft
Structure	Marine Plywood / Alum
Floor Support	(16) 7,000 lbs jacks

Other:

Install Time	30 min - 1 hr
Personnel Required	2
Site Prep	None
Hauling Mode	Pick-up Truck
Power Source	5 HP Gas Motor
Secondary Power (optional)	1.5 HP electric motor