M1	COMPOSITE METAL PANEL 1
3/8" = 1'-0"	

K1	COMPOSITE METAL PANEL 2
3/8" = 1'-0"	

G1	STONE PANEL / COMPOSITE METAL PANEL 3
3/8" = 1'-0"	

G4	SOUTHEAST ELEVATION
1/8" = 1'-0"	

NOTE: SEE ELEVATION G1-M1/AE202 FOR TYPICAL COMPOSITE METAL PANEL AND STONE DIMENSIONS

A1	SOUTHWEST ELEVATION
1/8" = 1'-0"	

GLAZING LEGEND:

- GL-1: 1" THICK IGU IN STOREFRONT SYSTEM ST1
- GL-2: 1 3/4" THICK IGU IN CURTAINWALL SYSTEM CW1
- GL-3: 1 3/4" THICK SPANDREL PANEL CURTAINWALL SYSTEM CW1
- GL-4: FROSTED INTERIOR SINGLE PANE GLASS
- GL-5: CLEAR INTERIOR SINGLE PANE GLASS

KEYNOTES:

E1	INFILL EXISTING CURTAINWALL LOCATION WITH NORMAN BRICK TO MATCH EXISTING
E3	4'-8" X 2'-10" SURFACE MOUNTED, LED DISPLAY CASE
E5	WINDOW FILM SIGN, DESIGN AND LOCATION TO BE COORDINATED WITH EXTERIOR SIGNAGE CONSULTANT
E6	CLEAN AND RE-POINT EXISTING BRICK WALL AS REQUIRED
E8	PROVIDE EMERGENCY EGRESS AT NEW ALLY FENCE. SEE CIVIL
E9	REPLACE EXISTING CORNER GUARD
E11	NEW METAL CANOPY
E12	INTERNALLY LIT BUILDING SIGNAGE. GC TO COORDINATE POWER REQUIREMENTS AND DESIGN WITH EXTERIOR SIGNAGE CONSULTANT
E13	HALO LIT BUILDING SIGNAGE LOCATION. GC TO COORDINATE POWER REQUIREMENT AND DESIGN WITH EXTERIOR SIGNAGE CONSULTANT
E14	NEW METAL COPING, ENTIRE ROOF
E17	WINDOW HEAD AND JAMB TO ALIGN WITH METAL PANEL SEAMS, TYP
E20	PATCH BRICK AT EXISTING LIGHT REMOVAL LOCATIONS
E22	FULL ANCHORED STONE PANEL TO ALIGN WITH BOTTOM OF CANOPY
E23	WINDOWS TO FIT WITHIN STONE PATTERN
E24	SPECIALTY DOOR HANDLES TO BE COORDINATED WITH BRANDING CONSULTANT AND TO MEET ALL APPLICABLE CODES
E25	DOOR TO BE CENTERED IN STONE PANELS
E26	PANEL LAYOUT POINT FOR COURSING IS TOP OF PARAPET
E27	METAL ACCENT STRIP TO MATCH CANOPY TO EXTEND DOWN FACE OF 4" BRICK WALL STEP
E28	METAL PANEL AND CANOPY TO ALIGN WITH ANCHORED STONE PANEL SEAM
E29	CURTAINWALL HEAD, SILL AND JAMBS TO ALIGN WITH METAL PANEL SEAMS
E31	CENTER RAIN WATER DOWNSPOUT NOZZLE IN PANEL. SEE MEP.
E32	COORDINATE HOSEBIB LOCATION WITH BRICK COURSING, SEE MEP
E33	FIRE DEPARTMENT CONNECTION

GENERAL NOTES:

1. ALL WALL PARTITION TYPES ARE M4 UNLESS NOTED OTHERWISE. SEE SHEET AE603 & AE604 FOR PARTITION TYPES.

2. REFER TO GI002 SHEET FOR ALL ABBREVIATIONS AND SYMBOLS.

3. REFER TO ALL DRAWINGS INCLUDING ARCHITECTURAL, CIVIL, STRUCTURAL, MECHANICAL, PLUMBING, AND ELECTRICAL DRAWINGS FOR ADDITIONAL GENERAL NOTES, ABBREVIATIONS, AND SYMBOLS

4. VERIFY ALL EQUIPMENT OPENINGS & RECOMMENDATIONS. LOCATION AND SIZES SHOWN ARE FOR INTENT PURPOSES ONLY. ADJUST ROUGH OPENINGS AND LOCATIONS AS REQUIRED PER ACTUAL EQUIPMENT.

5. G.C. TO PROVIDE & INSTALL ALL IN-WALL OR IN-CEILING BLOCKING / BRACING AS REQUIRED FOR ALL MILLWORK ITEMS, EQUIPMENT, SHELVING, AND ACCESSORIES WHETHER ITEMS ARE BY G.C. OR OTHERS COORDINATE WITH OWNER

6. G.C. SHALL BE RESPONSIBLE FOR LAYING OUT THE SPACE PRIOR TO COMMENCING WORK AND SHALL NOTIFY THE ARCHITECT AND OWNER OF ANY DISCREPANCIES.

7. ALL CONCRETE MASONRY UNITS AND MORTAR TO INCLUDE AN INTEGRAL WATER REPELLENT

8. ALL EXTERIOR DIMENSIONS ARE TO FACE STUD AND / OR FACE OF FOUNDATION AND MASONRY UNLESS SPECIFICALLY NOTED OTHERWISE.

9. ALL INTERIOR DIMENSIONS SHOWN ARE TO FACE OF FRAMING UNLESS SPECIFICALLY NOTED OTHERWISE

10. REFER TO SHEET GI003-005 FOR CODE COMPLIANCE PLAN, CODE REFERENCE INFORMATION AND FIRE RATED PARTITIONS AND SPACES. ALL MECHANICAL, ELECTRICAL, SPRINKLER AND PLUMBING PENETRATIONS THROUGH FIRE RATED CONSTRUCTION SHALL BE SLEEVED, FIRE SAFED AND / OR HAVE FIRE DAMPERS EQUIVALENT TO THE HOURLY FIRE RATING OF THE CONSTRUCTION.

11. ALL DRAWINGS ARE OF EQUAL IMPORTANCE IN DEFINING THE WORK OF THE CONTRACT DOCUMENTS. CONTRACTORS SHALL REVIEW ALL DRAWINGS BEFORE THE INSTALLATION OF THEIR WORK. SHOULD THERE BE A DISCREPANCY WITHIN AND BETWEEN THE DRAWINGS THAT WOULD CAUSE AN AWKWARD OR IMPROPER INSTALLATION NOTIFY ARCHITECT FOR CLARIFICATION PRIOR TO INSTALLATION OF SAID WORK. ANY WORK INSTALLED IN CONFLICT WITH THE ARCHITECTURAL DRAWINGS, SHALL BE CORRECTED BY CONTRACTOR AT THEIR EXPENSE AND AT NO ADDITIONAL COST TO THE OWNER OR ARCHITECT.

12. DO NOT SCALE DRAWINGS, THE DRAWINGS ARE NOT NECESSARILY TO SCALE - USE GIVEN DIMENSIONS. CONTRACTOR SHALL VERIFY ALL CONDITIONS AND DIMENSIONS AT THE JOB SITE PRIOR TO THE START OF CONSTRUCTION. IF DISCREPANCIES ARE FOUND, NOTIFY ARCHITECT FOR CLARIFICATION BEFORE COMMENCING THE WORK.

13. DETAILS NOT SHOWN ARE SIMILAR IN CHARACTER TO THOSE SHOWN. WHERE SPECIFIC DIMENSIONS, DETAILS, OR DESIGN INTENT CANNOT BE DETERMINED CONSULT ARCHITECT BEFORE PROCEEDING WITH THE WORK.

14. ALL PITCHED FLOOR AREAS SHOWN WITH PITCH LINES SHALL SLOPE AT 1/4" PER FOOT UNLESS OTHERWISE NOTED, PROVIDE A SLAB DEPRESSION AT ALL FLOOR DRAINS WHERE PITCH LINES ARE NOT SHOWN ON PLAN.
15. FINISH FLOOR ELEVATIONS ARE TO TOP OF CONCRETE, UNLESS OTHERWISE NOTED.
16. INSTALL ALL RECESSED CABINETS, PANELS, BOXES LOCATED IN FIRE-RATED PARTITIONS TO MAINTAIN THE FIRE-RATED CONSTRUCTION
17. REFER TO MECHANICAL AND ELECTRICAL DRAWINGS AND MANUFACTURES TEMPLATE DRAWINGS FOR ALL MECHANICAL AND ELECTRICAL EQUIPMENT SUPPORTS, BOLT SETTING TEMPLATES, ISOLATIONS, SPRING ISOLATION, ETC. NOT SHOWN ON THE DRAWINGS
18. OWNER FURNISHED ITEMS THE G.C. SHALL COORDINATE AND PROVIDE ELECTRICAL, PLUMBING, AND MECHANICAL CONNECTIONS FOR ALL EQUIPMENT.

REV.	DESCRIPTION	DATE
1	ASI 046	06 DEC 2016
0	ISSUED FOR CONSTRUCTION	06 JUNE 2016

KEYPLAN

PROJECT NORTH

LICENSED ARCHITECT JOCELYN R. BOOTHE No. 4238 STATE OF MAINE

WBRC
ARCHITECTS ENGINEERS
WWW.WBRCAE.COM
BANGOR, MAINE 207-947-4511
PORTLAND, MAINE 207-828-4511
SARASOTA, FLORIDA 941-556-0757

PROJECT: ASYLUM

BUILDING ELEVATIONS

SHEET TITLE:

WBRC CAD FILE: C:\Users\jocelyn.boothe\Documents\4071\10 - ASYLUM DANCE CLUB - ARCH_jocelyn.boothe.rvt

PROJECT No: 4071.10

SCALE: As indicated

PROJECT MANAGER: JRB

DRAWN BY: JRB

CHECKED BY: JET/MEJ

GRAPHIC SCALE: 0" 1"

SHEET No. AE202

COPYRIGHT 2007 WBRC

Inspections Division Date: 02/03/17

12/7/2016 8:50:33 AM C:\Users\jocelyn.boothe\Documents\4071\10 - ASYLUM DANCE CLUB - ARCH_jocelyn.boothe.rvt