

- A2-G15 Untempered Supply Unit with 15" Blower in Size #2 Housing x1  
Supply Fan handles 4532 CFM @ 0.500" wc ESP, Fan runs at 646 RPM.  
Supply Motor: 2.000 HP, 1 Phase 230 V, 60Hz, 9.3 FLA, ODP (Open Drip  
Proof)  
Down Discharge - Air Flow Right -> Left
- Sloped Filtered Intake for Size #2 Modular Untempered Supply Unit. x1  
26.813" Wide X 53.625" Long X 31.313" High.  
Includes 2" MV EZ Kleen Metal Mesh Filters.
- Gravity Back Draft Damper 22" X 24" , Standard Galvanized Construction, 1 x1  
1/4" Rear Flange, for Size 2 Untempered Fan Housing (5182)
- Curb CRB31X24 On Fan # 3 Flat Curb x1

**Electrical System #1**

- SC-221110FP 220V 1 Phase w/ control for 2 Exhaust Fans, 1 Supply Fan, x1  
Exhaust on in Fire, Lights out in Fire, Fan(s) On/Off Thermostatically  
Controlled. Room temperature sensor shipped loose for field installation.  
Includes 2 Duct Thermostat kits.
- Digital Prewire Lighting Relay Kit. Includes hood lighting relay & terminal x1  
blocks. Allows for up to 1400W of lighting each.
- Thermistor CABLE - 18/2 AWG GREEN WHITE, plenum rated. USED for x50  
thermistor duct stat. Per Foot Price.