

## Thermal and Shock Resistant Globe (L55 Fixture)

- Screw In Compact Fluorescent Bulb, L55 Series E26 Canopy Light Fixture - High Temp Assembly, Includes Clear Thermal and Shock Resistant Globe x4
- EXHAUST RISER - Field Cut 10" X 27" x1
- FIELD CUT, NOT PROVIDED - SUPPLY RISER - 12"x 28" Supply Riser with Volume Dampers x3
- 1/2 Pint Grease Cup New Style, Flanged Slotted x2
- FIELD WRAPPER 6.00" High Front, Right x1
- RIGHT VERTICAL END PANEL 27" Top Width, 21" Bottom Width, 80" High Insulated 4" Legs 430 SS x1
- Electrical Package Installation in Utility Cabinet by Plant. x1

**Fan #1 NCA16FA - Exhaust Fan**

- NCA16FA Belt Drive Centrifugal Upblast Exhaust Fan with 18.75" wheel Exhaust Fan handles 2833 CFM @ -0.850" wc ESP, Fan runs at 1010 RPM. Exhaust Motor: 1.500 HP, 1 Phase 230 V, 60Hz, 10.2 FLA, ODP (Open Drip Proof) x1
- Grease Cup for kitchen-duty centrifugal exhaust fans, Box Dimensions 15-3/4 L X 5-1/16 W X 3-3/4 H (18 GA.) (Includes Down Spout) x1
- Gasketing - Thermeez Woven Ceramic Tape - 1/4" x 1" with adhesive back - Max Temp 1500°F. To be applied between fan base and grease duct. Ships loose with fan. Gasket length supplied = perimeter of fan base. x1
- Curb CRB26.5x24E On Fan # 1 Flat Curb x1
- Hinged Base for Curb. Standard Hinge attached to curb. Used on Fans with wheels 20 inches or smaller. 12 GA Galvanized. x1
- Vented Base for Curb x1

**Fan #2 NCA16FA - Exhaust Fan**

- NCA16FA Belt Drive Centrifugal Upblast Exhaust Fan with 18.75" wheel Exhaust Fan handles 2833 CFM @ -0.850" wc ESP, Fan runs at 1010 RPM. Exhaust Motor: 1.500 HP, 1 Phase 230 V, 60Hz, 10.2 FLA, ODP (Open Drip Proof) x1
- Grease Cup for kitchen-duty centrifugal exhaust fans, Box Dimensions 15-3/4 L X 5-1/16 W X 3-3/4 H (18 GA.) (Includes Down Spout) x1
- Gasketing - Thermeez Woven Ceramic Tape - 1/4" x 1" with adhesive back - Max Temp 1500°F. To be applied between fan base and grease duct. Ships loose with fan. Gasket length supplied = perimeter of fan base. x1
- Curb CRB26.5x24E On Fan # 2 Flat Curb x1
- Hinged Base for Curb. Standard Hinge attached to curb. Used on Fans with wheels 20 inches or smaller. 12 GA Galvanized. x1
- Vented Base for Curb x1

**Fan #3 A2-G15 - Supply Fan**