

CITY OF PORTLAND
 FIRE PREVENTION BUREAU
 380 Congress Street, Portland, Maine 04101
 fireprevention@portlandmaine.gov
 (207) 874-8400

NOTICE OF VIOLATION AND ORDER TO CORRECT

TIMOTHY ROBINSON
 62 HAMPSHIRE ST #1R
 PORTLAND ME 04101

March 15, 2018

Location 62 HAMPSHIRE ST	CBL 028 C009001	Inspection Date 2/7/2018
Inspector Sean Donaghue	Inspection Type FP Routine Inspection	Status Failed

The City of Portland Fire Department inspected this property, and found the fire and life safety code violations listed below, which you are hereby ordered to correct. You must propose a date of completion to remedy each violation, a final date of completion, and a date of re-inspection.

You must send this form to the Fire Prevention Bureau no later than 3/30/2018.

Your failure to submit a plan of action by the date provided, or to correct any violation within the applicable time frame, may result in legal action against you, the imposition of civil penalties, and the pursuit of other legal remedies.

Violation	Proposed Date of Completion
PORTLAND FIRE DEPARTMENT CHAPTER 10 4.6.1, 4.6.2 UNIT/SUITE NUMBERS NOT MARKED; 4.6.1 Residential units shall be designated using numerals. 4.6.2 The first numeral of each residential unit shall be the floor designation. All unit doors, front and rear stairwell, must be identified properly on doors	___/___/___
NFPA 101- 7.5.1.1 EXIT OBSTRUCTED; Where exits are not immediately accessible from an open floor area, continuous passageways, aisles, or corridors leading directly to every exit shall be maintained and shall be arranged to provide access for each occupant to not less than two exits by separate ways of travel, unless otherwise provided in 7.5.1.1.3 and 7.5.1.1.4. Unit 2 Rear secondary egress to rear stairwell completely blocked with storage, no storage permitted in egress hallway	IMMEDIATELY remove all obstructions from the exits. Your signature below indicates that all obstructions have been removed and will not be replaced.
NFPA 101- 7.2.1.8.1 FIRE DOORS MUST BE SELF- OR AUTO-CLOSING; A door leaf normally required to be kept closed shall not be secured in the open position at any time and shall be self-closing or automatic-closing in accordance with 7.2.1.8.2, unless otherwise permitted by 7.2.1.8.3. All fire doors throughout building must be self closing, most were noted to not auto-close.	___/___/___
NFPA 101- 7.2.8.5.1 HANDRAILS REQUIRED ON STAIRS; All fire escape stairs shall have walls or guards and handrails on both sides in accordance with 7.2.8.4.1 (b). Secondary egress in rear requires handrail and repair to missing bollisters	___/___/___
NFPA 720- 5.5.6.1 CO ALARMS REQUIRED; The performance, location, and mounting of notification appliances used to initiate or direct action, evacuation or relocation of the occupants, or for providing information to occupants or staff, shall comply with the requirements of Chapter 6. Combination photoelectric hardwired co and smoke alarms with battery back up are required in the common area of each unit.	IMMEDIATELY install temporary alarms where required. Your signature below indicates that temporary alarms have already been installed.

Violation	Proposed Date of Completion
<p>NFPA 101- 31.3.4.5.1 SMOKE ALARMS REQUIRED; In buildings other than those equipped through out with an existing, complete automatic smoke detection system, smoke alarms shall be installed in accordance with 9.6.2.10, as modified by 31.3.4.5.2, outside every sleeping area in the immediate vicinity of the bedrooms and on all levels of the dwelling unit, including basements.</p> <p>Hardwired photoelectric Smoke alarms with battery back-up are required in every sleeping area, both bedrooms in unit 1 noted to be missing smokes in the sleeping area. Please ensure every sleeping area in every unit has a smoke detector. Also, there needs to be the same style smoke alarm outside each sleeping room.</p>	<p>IMMEDIATELY install temporary alarms where required. Your signature below indicates that temporary alarms have already been installed.</p>
<p>NFPA 101- 31.2.4.1 TWO EXITS REQUIRED ABOVE FIRST FLOOR; Every dwelling unit shall have access to not less than two separate exits remotely located from each other as required by 7.5.1.</p> <p>Unit 3F egress to fire escape is questionable. Double hung window egress area is small. Access to fire escape is not direct from window, roof and gutter are in between the window and the fire escape.</p>	<p>___ / ___ / ___</p>
<p>NFPA 70- ARTICLE 110.12 B EXPOSED WIRING CONNECTIONS; Internal parts of electrical equipment, including busbars, wiring terminals, insulators, and other surfaces, shall not be damaged or contaminated by foreign materials such as paint, plaster, cleaners, abrasives, or corrosive residues. There shall be no damaged parts that may adversely affect safe operation or mechanical strength of the equipment such as parts that are broken; bent; cut; or deteriorated by corrosion, chemical reaction, or overheating.</p> <p>Basement near rear washer and dryer, orange wire exposed connections</p>	<p>___ / ___ / ___</p>
<p>NFPA 70- 590.6 EXTENSION CORDS; Ground-fault protection for personnel for all temporary wiring installations shall be provided to comply with 590.6(A) and (B). This section shall apply only to temporary wiring installations used to supply temporary power to equipment used by personnel during construction, remodeling, maintenance, repair, or demolition of buildings, structures, equipment, or similar activities.</p> <p>By front basement stairwell/washer&dryer, used for area lighting. Please remove cords and install appropriately wired lighting.</p>	<p>___ / ___ / ___</p>
<p>NFPA 70 MISSING BOX COVERS; Refer to NFPA 70, National Electrical Code, on standards for missing box covers.</p> <p>Multiple noted throughout basement</p>	<p>___ / ___ / ___</p>
<p>NFPA 101- 8.3.4.2 60 MINUTE FIRE DOOR REQUIRED; Refer to NFPA 101- Table 8.3.4.2 that states fire door assemblies for vertical shafts (including stairways, exits, and refuse chutes) are rated and required for 1 hour.</p> <p>Basement, front and rear stairwells. All doors unit doors throughout building must be 60 minute rated fire doors with self-closing hardware.</p>	<p>___ / ___ / ___</p>
<p>FINAL DATE OF COMPLETED VIOLATION(S)</p>	<p>___ / ___ / ___</p>
<p>FIRE PREVENTION BUREAU RE-INSPECTION OF COMPLETED VIOLATION(S)</p>	<p>___ / ___ / ___</p>

The Bureau reserves the right to reject or modify any proposed plan of action, and may require evidence of sufficient financial and technical capacity to complete the proposed plan. Please contact the Bureau with any questions.

VIOLATOR CERTIFICATION

I agree to remedy the violations listed within the timeframes provided. If I require additional time to comply, I understand that I must contact the Fire Prevention Bureau prior to the deadline to request an extension, which is entirely within the Bureau's discretion to grant or deny.

I further understand that it is my responsibility to schedule a reinspection of my property once the violations have been remedied to do so. My failure to schedule a reinspection shall be deemed an admission that the violations have not been remedied.

If I fail to comply with this agreement, I understand that I am liable for penalties pursuant to the City of Portland Code of Ordinances §§ 1-15 and 10-25, and 30-A M.R.S. § 4452 and may be subject to further legal action.

Date

Responsible Party

Date

Responsible Party

SEEN AND AGREED

Date

Fire Prevention Bureau