HAMPSHIRE STREET

PLANT LIST

TREES & SHRUBS

KEY	COMMON & BOTANICAL NAME	SIZE	ROOT	QTY	NOTES
A	STREETKEEPER HONEYLOCUST G. TRIACANTHOS Var. 'inermis' 'Streetkeeper'	2 ½ " Cal.	B&B	9	Trim for 8' clear under branches
B	NORTHERN BAYBERRY M. PENSYLVANICA	18-24" HT.	PTD	8	
C	FRAGRANT SUMAC RHUS AROMATICA 'Gro-Low'	#2	CONT	12	
D	SHASTA VIBURNUM V.PLICATUM VAR. Tomentosum 'Summer Snowflake'	#5	B&B	8	
E	GREEN CARPET JUNIPER J. SABINA	#3	CONT	14	

PERENNIALS

AA	SWITCH GRASS PANICUM VIRGATUM 'Cheyenne sky'		—	25	@18" O.C.
BB	SWITCH GRASS PANICUM VIRGATUM ' Shenandoah'		—	25	"
CC	DAYLILY VAR. HEMEROCALLIS		PTD	80	BLOOM IN JULY THRU SEPT 18" O.C.
DD	HOSTA 'BIG DADDY'		—	13	

PLANTING NOTES

1. The contractor shall supply all plants in quantities sufficient to complete the work shown on plan. Any discrepancies between quantities shown on plant list and those required by this drawing shall not entitle contractor to additional remuneration.
2. Any plant substitutions must be approved by the owner.
3. Any tree or shrub which comes over or under any utility shall be relocated on the site by the landscape architect.
4. All lawn areas to have 6" of topsoil unless noted otherwise.
5. All trees and shrubs shall be placed in the designated areas as shown on the plan and before planting shall be approved by the landscape architect.
6. The contractor shall relocate any tree or shrub as directed by the landscape architect.
7. All plant material installed shall meet the specifications of the American Standard for Nursery Stock (latest edition) as set forth by the American Association of Nurserymen.
8. The landscape contractor shall replace or repair to original condition any and all utilities, paving, curbing, etc., damaged as a result of their operations at no additional cost to the owner.

PRELIMINARY - NOT FOR CONSTRUCTION

REGISTERED LANDSCAPE ARCHITECT ANTHONY MUENCH No. 7 12-22-17 State of Maine

DATE:			