Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 09/11/17

DEMOLITION PLAN

1/4" = 1' - 0"

REGISTERED ARCHITECT
MARK M. WILCOX
No. 1299
STATE OF MAINE

DEMO KEYED NOTES

1. REMOVE METAL STUD FRAMED DRYWALL PARTITION.
2. REMOVE EXISTING CARPETING IN THIS ROOM. REMOVE GLUE RESIDUE. GRIND CONC SMOOTH. REMOVE EXISTING VINYL BASE AT WALLS TO REMAIN AND PATCH WALLS TO MATCH EXISTING.
3. REMOVE EXISTING ACT CEILING TILES AND GRID IN THIS ROOM.
4. REMOVE DOOR AND FRAME. SAVE DOOR, HINGES, LOCKSET AND FLOOR STOP FOR REUSE.
5. EXISTING VAV UNIT TO REMAIN.
6. REMOVE METAL STUDS AND DRYWALL AND PREPARE NEW ROUGH OPENING FOR PROPOSED DOOR.
7. CUT AND PATCH EXISTING DRYWALL FOR PLUMBING

0 8 16

NORTH

EXAM ROOMS RENOVATIONS

Portland Family Practice

Maine Health
Portland, Maine

DEMOLITION PLAN

WINTON SCOTT ARCHITECTS
5 Milk Street
Portland, Maine 04101

Scale: 1/4" = 1' - 0"

PRINT ON 16 X 24

D 1

5 | 12 | 17