Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 09/11/17

T 1 — 6" = 1'-0"

H 1 J 1 — 3" = 1'-0"

1 **EXAM ROOM ELEVATION**
3/8" = 1' - 0"

D1
- PLAIN SLICED WHITE OAK
- CLEAR FINISH
- LIFETIME WARRANTY

DOOR TYPES

3/8" = 1' - 0"

F1 WELDED HOLLOW METAL

FRAME TYPES

3/8" = 1' - 0"

MILLWORK NOTES

HPDL	0.050 HORIZ GRADE PLASTIC LAMINATE CHARTER OR EQUAL 3MM PVC EDGING TO MATCH HPDL AT DOOR AND DRAWER EDGES
LPL	PREFINISHED MELAMINE PANEL FOR CABINET INTERIORS
HINGES	EUROPEAN CONCEALED
PULLS	3" ALUM WIRE PULLS

HARDWARE SETS

HW 1
- SALVAGED HINGES
- SALVAGED CYLINDRICAL LOCKSET
- SALVAGED FLOOR STOP

HW 2
- BALL BEARING HINGES
- LOCKSET 10 LINE TO MATCH EXISTING
- ENTRY FUNCTION TO MATCH EXISTING
- CYLINDER + KEYING
- FLOOR STOP

2 **EXAM ROOM ELEVATION**
3/8" = 1' - 0"

DOOR AND FRAME SCHEDULE

			DOOR			FRAME								
DOOR NO.	SIZE	THICK	MATL	FINISH	TYPE	MATL	FINISH	TYPE	JAMB	HEAD	SILL	HARDWARE	LABEL	REMARKS
233	3' 0" x 6' 8"	1 3/4"	WD	NAT	D1	HM	PTD	F1	J1	H1	T1	HW 1	-	
234A	3' 0" x 6' 8"	1 3/4"	WD	NAT	D1	HM	PTD	F1	J1	H1	T1	HW 1	-	
234B	3' 0" x 6' 8"	1 3/4"	WD	NAT	D1	HM	PTD	F1	J1	H1	-	HW 2	-	
235	3' 0" x 6' 8"	1 3/4"	WD	NAT	D1	HM	PTD	F1	J1	H1	T1	HW 1	-	

EXAM ROOMS RENOVATIONS
Portland Family Practice

Maine Health
Portland, Maine

INTERIOR ELEVATIONS / DOOR SCHEDULE

WINTON SCOTT ARCHITECTS
5 Milk Street
Portland, Maine 04101

Scale: AS SHOWN

A 3

5 | 12 | 17