ELEV. STAIR A ROOM 9'-0" CLG 9'-0" CLG 210 9'-0" CLG +/- 9'-5" CLG +/- 9'-5" CLG GYP AS PART OF FLOOR/ CEILING ASSEMBLY -+/- 10'-0" CLG UNIT UNIT 206 204 203 202 GYP AS PART OF FLOOR/ GYP AS PART OF FLOOR/ GYP AS PART OF FLOOR/ GYP AS PART OF FLOOR GYP AS PART OF FLOOR/ CEILING ASSEMBLY -+/- 10'-0" CLG CEILING ASSEMBLY -+/- 10'-10" CLG CEILING ASSEMBLY -+/- 10'-10" CLG CEILING ASSEMBLY -CEILING ASSEMBLY -, +/- 10'-10" CLG. ⁻ .` +/- 10'-10" CLG, ` REFER TO ELECTRICAL PLANS FOR LIGHTING LAYOUTS

GENERAL NOTE:

- 1. ARCHITECTURAL CEILING PLANS DO NOT SHOW ALL PROJECT LIGHTS. SEE LIFE SAFETY PLANS FOR LIFE SAFETY FIXTURES AND ELECTRICAL PLANS FOR ADDITIONAL FIXTURES.
- 2. LIGHTS OR CEILING ELEMENTS NOT DIMENSIONED AND GRAPHICALLY SHOWN AS CENTERED IN A SPACE OR CENTERED ON A WALL OR ELEMENT ARE TO BE LOCATED CENTERED IN THAT SPACE OR ON THAT ELEMENT.
- 3. PROVIDE FULL LENGTH UNDERCOUNTER LIGHTS FOR ALL PROJECT UPPERS
- 4. CENTER VANITY SCONCES ABOVE VANITIES U.N.O.

5. TRACK LIGHTING LOCATION WITHIN UNITS - WHEN LOCATED ALONG A LENGTH OF WALL AND NOT DIMENSIONED OTHERWISE HOLD TRACK LIGHTING AND WALL WASHERS 2'-0" OFF OF WALL SURFACE.

6. IN UNITS WHERE A FIREPLACE IS SELECTED CENTER TRACK LIGHTING ON FIREPLACE. CONTRACTOR TO CONFIRM WITH ARCHITECT PRIOR TO PURCHASE/ INSTALLATION

7. HOODS ARE TO BE CENTERED ABOVE RANGES. CONTRACTOR TO VERIFY RANGE AND HOOD LOCATIONS AS

- 8. SEE ELECTRICAL DRAWINGS FOR FIXTURE TYPE.
- 9. PROVIDE CLOSET LIGHTING AS NOTED IN ELECTRICAL DRAWINGS.

RCP LEGEND

FIR T&G CEILING GYPSUM CEILING - SEE FLOOR ASSEMBLY FOR HEIGHT OFF DECK GYPSUM CEILING - 9'-0" A.F.F.

GYPSUM CEILING - 8'-6" A.F.F.

LIGHT FIXTURE - ABOVE/UNDER CABINET LIGHTING

- LIGHT FIXTURE JUNCTION BOX (TRACK OPTION)
- LIGHT FIXTURE SURFACE MOUNTED
- LIGHT FIXTURE WALL SCONCE LIGHT FIXTURE - RECESSED LIGHT
- JUNCTION BOX

Date:		
A	7	

21,

2ND