ASHP Site Plan

Outdoor Unit
(1) Mitsubishi MXZ-3C24NAHZ -- 187 lbs
Installation: Concrete foundation
Location: Rear – adjacent to parking lot
Indoor Unit
(2) Mitsubishi MSZ-FH12 - 29 lbs
Installation: Wall-Mounted

The home is built of wood framing with brick exterior and should be sufficient to support the additional load of the equipment being installed.

Inspections Division
Date: 11/06/17

142 Presumpscot St
Portland, ME 04103
(207) 221-6342

Client:

Molly McIntyre

Project Address:

76 India St
Portland, ME 04108

System Type:

Air Source Heat Pump

Not For Construction

Designed by:	DR
Revision:	0
Print Size:	8.5" x 11"
Scale:	NTS
Date:	October 26, 2017

SITE PLAN

Sheet A01

© Copyright ReVision Energy

This diagram is provided as a service and is based on the understanding of the information supplied. It is subject to change based on actual conditions, applicable edition of the National Electric Code, and local governmental authorities.