2 PARTIAL RAMP PLAN
3/8" = 1'-0"

3 PARTIAL WALL FRAMING PLAN
3/4" = 1'-0"

4 BENCH FRAMING PLAN
1/2" = 1'-0"

5 ADA BENCH FRAMING PLAN
1/2" = 1'-0"

1 PARTIAL WALL FRAMING PLAN
3/8" = 1'-0"

PLAN NOTES:

1. "S1" DENOTES LIGHT- GAGE WALL. SEE SCHEDULE ON THIS SHEET.
2. H1 DENOTES BUILT-UP LIGHT-GAGE HEADER, SEE SCHEDULE ON THIS SHEET.
3. VERIFY ALL DIMENSIONS w/ ARCH.

WALL TYPES

MARK	STUD TYPE	SPACING	MAX. WALL HEIGHT
S1	3625162-33 STEEL STUDS (20 GAGE)	16" o.c.	NA
S2	6005162-33 STEEL STUDS (20 GAGE)	16" o.c.	NA

NOTES:

1. SEE SECTIONS AND DETAILS FOR THICKNESS OF TOP & BOTTOM TRACK SECTIONS.
2. FASTEN GYP. BOARD SHEATHING TO STUDS w/ #6x 1 1/4" GYP.
3. COORDINATE WALL TYPES w/ ARCH.
4. SEE ARCH. DRAWINGS FOR STUD WALL SHEATHING. WHERE SHEATHING IS NOT CONTINUOUS BOTH SIDES FOR FULL HEIGHT OF WALL PROVIDE CONTINUOUS 16 GA. HORIZ. BRIDGING @ 24" o.c. VERT. ANCHOR BRIDGING TO STUDS WITH 16 GA. CLIP ANGLES WITH (2) #10 SCREWS TO STUDS AND BRIDGING.

LIGHT GAGE HEADER SCHEDULE

MARK	HEADER TYPE
H1	(2) 6005162-33 (20 GAGE)

NOTES:

1. SCREW MEMBERS TOGETHER w/ #10 TEK SCREWS @ 6" o.c.
2. SEE 4-6/5300 FOR ADDITIONAL INFORMATION.

ENGINEER/SEAL:

Date: 09/22/14

STATE OF MAINE
PAUL E STOLE
10481
LICENSED
PROFESSIONAL ENGINEER

NewStudio Architecture
4431 Lake Avenue South
White Bear Lake, MN 55110
p: 651.207.5527
f: 651.207.8247

NSA PROJECT NUMBER: 2013-99

ANTHROPOLOGIE

60 Pearl Street
Portland, ME 04101

STRUCTURAL ENGINEER:

AST
Advanced Structural Technologies
7212 Metro Blvd
Edina, MN 55439
(952) 854-9302 tel
(952) 854-9690 fax
www.astmn.com

© PROPERTY OF ADVANCED STRUCTURAL TECHNOLOGIES. THIS DOCUMENT MAY NOT BE USED OR COPIED WITHOUT THE PRIOR WRITTEN CONSENT OF ADVANCED STRUCTURAL TECHNOLOGIES.

DRAWN BY: AJM CHECKED BY: DCB

AST PROJECT NUMBER: ME 1001

PROJECT PHASE: CD

ISSUE / DATE:

100% CHECK SET	07-11-2014
BID/PERMIT	08-01-2014

REVISION :

SHEET TITLE :
PARTIAL FRAMING PLANS

SHEET NO :
S110