PROPOSED ELEVATION
1/8"=1'-0"

FACADE RENOVATION NOTES:

- (A) GRANITE PIERS TO REMAIN
- (B) METAL DECORATIVE COLUMNS WITH GRANITE REMAIN
- (C) GLASS STOREFRONT TO REMAIN, TYP.
- (D) GLASS STOREFRONT TO BE REMOVED
- (E) GRANITE FREEZE TO REMAIN
- (F) NO WORK AT BRICK FACADE
- (G) EXISTING FIRE DEPARTMENT CONNECTION EQUIPMENT TO REMAIN
- (H) PRESERVE GRANITE BASES, TYP.
- (I) EXISTING PANEL MOTIF TO BE REMOVED
- (J) REUSE EXISTING UNCOVERED GRANITE STEPS
- (K) FINAL PROPOSED SIGNAGE LOCATION BY TENANT (SEPERATE SIGN PERMIT BY TENANT TO BE APPROVED BY H.P.)
- (L) PROPOSED GLASS STOREFRONT (CLEAR GLAZING) TO MATCH EXISTING FACADE, PAINT COLOR TO MATCH EXISTING
- (M) PROPOSED PANEL MOTIF TO MATCH EXISTING IN STYLE & COLOR

CITY OF PORTLAND, MAINE — RESURGAM

Inspections Division
Date: 10/02/14

ARCHITECTS
A.I.A.
100 Commercial Street
Suite 205
Portland, Maine 04101
Phone: 207.774.9057
Email:
rf@lmuellerarchitects.com

© COPYRIGHT 2014
MARK MUELLER ARCHITECTS

PROPOSED WALL SECTION
3/4"=1'-0"

ENLARGED PROPOSED ELEVATION
1/4"=1'-0"

ENLARGED PROPOSED PLAN
1/4"=1'-0"

EAST BROWN COW

ADDENDA SET: AUGUST 04, 2014
BUILDING PERMIT SET: JULY 01, 2013

INTERIOR DEMOLITION:

ANTHROPOLOGIE

66 PEARL STREET
PORTLAND, MAINE

PROPOSED 1 TENANT SCHEME

REVISIONS	
DATE	JULY 2014
PROJECT	ANTHROPOLOGIE
DRAWN BY	MRP
CHECK BY	MLM

A-1.2