AREA OF NEW TENANT SPACE WORK

AREA OF NEW ENTRY VESTIBULE @ FACADE

KEY PLAN
1/16"=1'-0"

WALL LEGEND

- EXISTING WALL
- NEW WALL
- FIRE RATED WALL
- BRICK WALL
- 1 HOUR
- EXISTING WALL TO BE REMOVED

PROPOSED 1ST FLOOR PLAN
1/8"=1'-0"

PROPOSED WALL - INTERIOR

NOT USED

1 6" METAL WALL - (1HR RATED)
(UL DESIGN: U 419sim.) FIRE CAULK PERIMETER

- EXTEND WALL TO UNDERSIDE OF FLOOR SYSTEM ABOVE -

* INSTALL ALL MATERIALS PER MANUFACTURE REQUIREMENTS

PROPOSED WALL - INTERIOR

2 6" METAL WALL - (1HR RATED)
(UL DESIGN: U 419) FIRE CAULK PERIMETER

- EXTEND WALL TO UNDERSIDE OF FLOOR SYSTEM ABOVE -

* INSTALL ALL MATERIALS PER MANUFACTURE REQUIREMENTS

PROPOSED WALL - EXTERIOR

3 2x6 STUD WALL - (NON-RATED)
CAULK PERIMETER

* INSTALL ALL MATERIALS PER MANUFACTURE REQUIREMENTS

LIFE SAFETY LEGEND:

- EMERGENCY BACKUP LIGHT
- EXIT — EXIT LIGHT
- SD — PHOTOELEC SMOKE DETECTOR
- HD — HEAT & CO DETECTOR
- HORN/STROBE
- STROBE
- FE — FIRE EXTINGUISHER IN RECESSED CABINET
- P S — PULL STATION - SPRINKLER SYSTEM

LIFE SAFETY NOTES:

-LIFE SAFETY AND FIRE ALARM SYSTEMS SHALL BE DESIGNED AND INSTALLED PER NFPA 72, BY A CITY/ STATE APPROVED CONTRACTOR WITH A SEPERATE PERMIT.

-ALL STROBES TO BE 30 CANDELA UNLESS OTHERWISE NOTED.

-SYSTEM SHALL BE SUPERVISED BY AN OFF-SITE CERTIFIED BY THE CITY OF PORTLAND THIRD PARTY

-EXISTING LIFE SAFETY SYSTEM SHALL REMAIN, TYP EACH SIDE

1 FLOOR/ CEILING ASSEMBLY (1 HR FIRE RATED)
(UL DESIGN: L526) FIRE CAULK PERIMETER

* INSTALL ALL MATERIALS PER MANUFACTURE REQUIREMENTS

OPENING SIZE*	LINTEL PER WYTHE	JAMB EXTENSION
LESS THAN 4'-0"	L3 1/2x 3 1/2x 1/4	4"
4'-1 TO 7'-6"	L5x 3 1/2 x 1/4 LLV	4"

* FOR OPENINGS GREATER THAN LISTED, SEE PLAN.
** ALL TEMPORARY SHORING BY G.C. -TYP.

NEW LINTEL INSTALLATION IN EXISTING BRICK
NO SCALE

EAST BROWN COW

ADDENDA SET: AUGUST 04, 2014
BUILDING PERMIT SET: JULY 01, 2013

CITY OF PORTLAND, MAINE — RESURGAM

Inspections Division
Date: 10/02/14

A.I.A.
100 Commercial Street
Suite 205
Portland, Maine 04101
Phone: 207.774.9057
Email:
rfi@muellerarchitects.com

© COPYRIGHT 2014
MARK MUELLER ARCHITECTS

INTERIOR DEMOLITION: ANTHROPOLOGIE
66 PEARL STREET
PORTLAND, MAINE

PROPOSED FLOOR PLAN

REVISIONS
DATE
JULY 2014
PROJECT
ANTHROPOLOGIE
DRAWN BY
MRP
CHECK BY
MLM

A-1.1