

R.J. ENTERPRISES, Inc.
P.O. Box 82
Brunswick, ME 04011
207-373-0344 (Ph) /207-373-1344 (Fax)

May 22, 2013

Thomas B. Federle
Federle Mahoney, LLC
254 Commercial Street
Portland, ME 04101

RE: Asbestos abatement certification

On May 21, 2013, R.J. Enterprises completed the abatement of asbestos containing material from the basement and from the exterior of the house located at 160 Newbury Street in Portland, Maine.

In the basement there was much asbestos debris and pipes covered with asbestos. The exterior of the building was sided with an asbestos containing asphalt siding.

In the basement, the work area was placed under negative pressure by covering critical barriers with 6-mil polyethylene and installing a HEPA equipped negative air machine. A three stage decontamination unit was attached directly to this containment. Workers in full personal protective equipment and proper respiratory protection cleaned the entire basement of asbestos material. Air sampling at the conclusion indicated a safe environment.

The exterior of the building was accessed by a man lift and ladders. The work area was isolated by barrier tape and workers wore full PPE. All waste was placed into a double lined dumpster for proper disposal into an E.P.A. approved landfill.

All asbestos work was accomplished according to all Federal and State rules and regulations using state-of-the-art equipment and techniques.

If you have any questions, please do not hesitate to call.

Sincerely,



Richard Giberson