



# 62 INDIA STREET (HEBERT CONSTRUCTION)

December 27, 2017

## NFPA 1, 101 & 220 2009: CODE DATA

USE GROUP CLASSIFICATION	BUSINESS (B)
TYPE OF CONSTRUCTION	V (1,1,1)
NET USEABLE AREA	1,428 SF
PROPOSED BUILDING AREA	ETR
LOT AREA	ETR
PROPOSED BUILDING HEIGHT (STORIES/ FEET)	ETR (SINGLE STORY TENANT SPACE)
BUILDING AREA LIMITATION - SQ FT	NONE
BUILDING HEIGHT LIMITATION - STORIES	NONE
TRAVEL: COMMON PATH LIMIT (ALLOWABLE/ ACTUAL)	BUSINESS 100' (ACTUAL = LESS THAN ALLOWABLE)
TRAVEL: DEAD-END LIMIT (ALLOWABLE/ ACTUAL)	BUSINESS 50' (ACTUAL = LESS THAN ALLOWABLE)
TRAVEL: EXIT ACCESS TRAVEL DISTANCE LIMIT (ALLOWABLE/ ACTUAL)	MERCANTILE 300' (ACTUAL = LESS THAN ALLOWABLE)
FIRE SUPPRESSION SYSTEM	NFPA 13
NUMBER OF REQUIRED EXITS	ONE (TWO PROVIDED)
<b>EXIT ACCESS FIRE RATINGS</b>	
FIRE WALLS/ BARRIERS	2 HOUR AT PARKING GARAGE TO ADJACENT UNITS
OCCUPANCY SEPARATION	2 HOUR (R-2)
TENANT SEPARATION	1 HOUR
PARTY WALLS	NONE
STAIR ENCLOSURES	2 HOUR
SHAFTS	2 HOUR
EXIT ACCESS CORRIDORS	30 MIN. (30.3.6.1.2)
TRASH ROOMS	1 HOUR (TABLE 30.3.2.1.1)
<b>FIRE PROTECTION OF STRUCTURE</b>	
COLUMNS	1 HOUR
BEAMS, GIRDERS, TRUSSES & ARCHES	1 HOUR
LOAD BEARING WALLS - EXTERIOR	1 HOUR
LOAD BEARING WALLS - INTERIOR	1 HOUR
NON-LOAD BEARING WALLS - EXTERIOR	0 HOUR
NON-LOAD BEARING WALLS - INTERIOR	0 HOUR
FLOOR CONSTRUCTION	1 HOUR
ROOF CONSTRUCTION	1 HOUR
<b>OCCUPANT LOAD</b>	
1ST FLOOR	
BUSINESS	1,428 SF      100 SF/ PERSON =      14
<b>GENERAL NOTES:</b>	
INTERIOR FINISHES:	
WALLS & CEILINGS: CLASS A, B, OR C	
FLOORS: CLASS 1 OR 2 - F.F.E. SHALL MEET NFPA 265 & 701.	