



- A** BRICK VENEER  
'OLD PORT' BLEND, MEDIUM RANGE BY  
MORIN BRICK IN AUBURN MAINE
- B** 10" CEMENTITIOUS SIDING
- C** GRANITE ENTABLATURE:  
THICKNESS: 2 1/2"  
SURFACE: ROCK FACE  
COLOR: DEER ISLE

- D** GRANITE PIERS:  
THICKNESS: 4"  
SURFACE: ROCK FACE  
COLOR: DEER ISLE

- E** GRANITE SILL:  
THICKNESS: 4"  
SURFACE: HONED  
COLOR: DEER ISLE

- F** MIXED USE FACADE FENESTRATION: WINDOWS  
MATERIAL: ALUMINUM  
FRAMES: 2" X 4 1/2"  
COLOR: CHARCOAL  
GLASS: CLEAR, 77% VLT, CENTER SET GLASS

- G** MIXED USE FACADE FENESTRATION: DOORS  
SIMILAR TO WINDOWS  
DOORS: STYLE AND RAIL TYPE  
GLASS: TRANSOMS AND FLANKING GLASS PANEL

- H** RESIDENTIAL WINDOWS:  
MANUFACTURE: PELLA  
SERIES: 450 PRO-LINE  
STYLE: DOUBLE HUNG W/ SDL  
MOULDINGS: METAL  
BRICK VENEER- 1 1/2" BRICKMOLD  
SIDING: ~3 1/2" BRICKMOLD  
SILLS: 2"  
GLASS: LOW 'E' 77% VLT, CENTER GLASS

- I** METAL CANOPY:  
MATERIAL: STEEL PANEL  
FINISH: PAINTED KYNAR  
THICKNESS: 22 GAUGE  
EXTENTS: WRAP ALL EXPOSED SIDES

- J** EXTERIOR DECKS:  
GUARDRAILS: ALUM. NEWEL POSTS  
AND BALUSTERS  
LIGHTING: LOW WALL MOUNT  
5 WATT LED FIXTURE, TYP. ALL DECKS



MARK  
MUELLER  
ARCHITECTS

INDIA STREET NEIGHBORHOOD  
HISTORIC PRESERVATION WORKSHOP

APRIL 20, 2016

62 INDIA STREET

A-2.0