ROOM FINISH SCHEDULE

AREA	FLOOR		WALLS	CEILING		DOORS		REMARKS
	MATERIAL	BASE	MATERIAL	MATERIAL	HEIGHT	DOOR	FRAME	
SALES AREA	VINYL FLOORING VCT-2	WOOD BASE B5	GYP. BD. AT FEATURE WALLS P1-SG)-PAINT FROM FLOOR TO EDGE OF SOFFIT P18 AT CURVED WALL WOOD COLUMNS WB-CUSTOM X WOOD BEAMS WB-CUSTOM X	MAIN CLG. – GYP. BD. P18	15'-8" A.F.F.			* USE USG LEVEL 5 FINISH FOR ALL CEILINGS AND WALLS * GC BUILT FEATURE WALLS W/ VENDOR PROVIDED STANDARDS * PAINT (E) COLUMNS P19-SG
FITTING AREA	VINYL FLOORING VCT-2	WOOD BASE B2 B5	-BEADBOARD BB2 W/ B2 BASE AND B3 TRIM P1-SG & GYP. BD. P1-EG ABOVE GYP. BD. AT FEATURE WALLS P1-SG	EXPOSED CEILING – CLEAN (E) FRAMING	7'-7" A.F.F.	P1-SG	P1-SG	* USE USG LEVEL 5 FINISH FOR ALL WALLS
STOCK/EMPLOYEE/ MANAGER'S AREA	(E) CONCRETE C01 C02	VINYL BASE B1	PLYWOOD P1-SG	(E) GYP. BOARD – P1-SG EXPOSED CEILING	–	P1-SG	P1-SG	
WOMEN'S/MEN'S TOILET	TILE T-3	TILE T-4	BB2 AND B3 P1-MG GYP. BOARD P1-MG	GYP. BD. P12-MG	9'-0" A.F.F.	P1-SG	P1-SG	* MRX GRADE BEADBOARD @ WET WALL & @ DRINKING FOUNTAINS * ALIGN BOTTOM OF TRIM B3 WITH TOP OF CHANGING TABLE
CORRIDOR	VINYL FLOORING VCT-2	WOOD BASE B2	-BEADBOARD BB2 W/ B2 BASE AND B3 TRIM P1-SG & GYP. BD. P1-EG ABOVE	GYP. BD. P2	9'-0" A.F.F.	P1-SG	P1-SG	* SEE BUILDING SECTION TO REFERENCE THE HEIGHT & EXTENT OF BEADBOARD * TILE T-3 FLOOR @ DRINKING FOUNTAINS * WOOD BASE B2 PAINTED P1-SG
MEZZANINE – BOH AREA	(E) CARPET	(E) BASE	(E) GYP. BOARD P1-EG	(E) GYP. BOARD P12	7'-1" A.F.F.			*PATCH & REPAIR (E) GYP. BOARD AS REQUIRED *PAINT EXPOSED SPRINKLER LINES TO MATCH CEILING
MOP SINK	(E) CONCRETE C01 C02	VINYL BASE B1	GYP. BD. P1-MG WAINSCOT WA-1	EXPOSED CEILING	–	P1-SG	P1-SG	* WAINSCOT WA1 TO 4'-0" A.F.F. – ALL WALLS * @ BOH, STOP FRONT WALL OF MOP SINK 6" ABOVE THE DOOR FRAME
CLOSET	(E) CONCRETE C01 C02	VINYL BASE B1	GYP. BD. P1-SG	EXPOSED CEILING	–	P1-SG	P1-SG	

NOTES:
1. WALLS TO BE PAINTED FLOOR TO CEILING U.O.N.
2. PAINT CEILING & ALL EXPOSED MEP ELEMENTS, EXCEPT DUCTS. DO NOT PAINT SIGN DROPS, UNISTRUT & THREADED RODS, U.O.N.
3. SEE PLANS & ELEVATIONS FOR EXACT FINISH LOCATIONS
4. SEE G0-2 FOR FINISH INFORMATION

GENERAL NOTES & ABBREVIATIONS

&	AND	CONT.	CONTINUOUS	FL.	FLOOR	MECH.	MECHANICAL	S.C.	SOLID CORE
<	ANGLE	C.P.M.	CONST. PROJECT MANAGER	FLUOR.	FLUORESCENT	MFR.	MANUFACTURER	S.S.	STAINLESS STEEL
@	AT	DBL.	DOUBLE	FT.	FOOT, FEET	MGR.	MANAGER	SHT.	SHEET
C	CENTERLINE	DET.	DETAIL	F.V.	FIELD VERIFY	MIN.	MINIMUM	SIM.	SIMILAR
O	DIAMETER	DIA.	DIAMETER	G.B.	GRAB BAR	MISC.	MISCELLANEOUS	SPEC.	SPECIFICATION
#	POUND OR NUMBER	DIM.	DIMENSION	B.C.	GENERAL CONTRACTOR	MTL.	METAL	SQ.	SQUARE
ACOUS	ACOUSTICAL	DN.	DOWN	GA.	GAUGE	N.	NORTH	STD.	STANDARD
ADJ	ADJUSTABLE	DR.	DOOR	GL.	GLASS	N.I.C.	NOT IN CONTRACT	STL.	STEEL
A.F.F	ABOVE FINISH FLOOR	DS	DOWNSPOUT	GYP.	GYPSUM	N.T.S.	NOT TO SCALE	STOR.	STORAGE
ALUM.	ALUMINUM	DWG	DRAWING	H.C.	HOLLOW CASE	(N)	NEW	SUSP.	SUSPENDED
ARCH.	ARCHITECTURAL	(E)	EXISTING	H.M.	HOLLOW METAL	M.	NUMBER	T.C.	TIME CLOCK
ATH.	ATHLETA	E.P.	ELECTRICAL PANEL BOARD	HC.	HANDICAPPED	NOM.	NOMINAL	T.O.	TOP OF
BD.	BOARD	EA.	EACH	HDWD.	HARDWOOD	O.D.	OUTSIDE DIAMETER	TEL.	TELEPHONE
BLDG.	BUILDING	ELEV.	ELEVATION	HORIZ.	HORIZONTAL	ORI	OWNER FURNISHED ITEM	THK.	THICK
BLK.	BLOCK	ELEC.	ELECTRICAL	HGT.	HEIGHT	OPNG.	OPENING	TYP.	TYPICAL
BLKG.	BLOCKING	EMER.	EMERGENCY	HR.	HOUR	OPP.	OPPOSITE	U.O.N	UNLESS OTHERWISE NOTED
BM.	BEAM	EQ.	EQUAL	H.T.	HANGER – TIGHT UNIT	P.LAM.	PLASTIC LAMINATE	VERT.	VERTICAL
BOH	BACK OF HOUSE	E.W.C.	ELEC. WATER COOLER	HVAC	HEATING, VENTILATION, AIR CONDITIONING	PL.	PLATE	V.I.O.	VERIFY IN FIELD
BOT.	BOTTOM	F.E.	FIRE EXTINGUISHER	I.D.	INSIDE DIAMETER	PLAS.	PLASTER	W.	WEST
BET.	BETWEEN	F.O.	FACE OF	INSUL.	INSULATION	PLYWO.	PLYWOOD	W/	WITH
BW.	BARN WOOD	F.O.F.	FACE OF FINISH	JT.	JOINT	PR.	PAIR	W/C	WATER CLOSET
CAB.	CABINET	F.O.S.	FACE OF STUDS	LAM	LAMINATE	PT.	POINT	W/O	WITHOUT
CER.	CERAMIC	F/F	FACE OF FINISH	LB(S)	POUNDS	R.	RISER	W/R	WATER RESISTANT
CL.	CENTERLINE	F.R.P.	FIBERGLASS REINFORCED PANEL FINISH	LL	LANDLORD	RAD.	RADIUS	WD.	WOOD
CLG.	CEILING	F.R.	FIRE RETARDANT	L.O.C	LOCATION	REG.	REGISTER	WT.	WEIGHT
CLKG	CAULKING	F.S.	FULL SIZE	LT.	LIGHT	REQ'D	REQUIRED		
CLR.	CLEAR	FIN.	FINISH	MIR.	MIRROR	RESIL.	RESILIENT		
COL.	COLUMN	FIT. RM.	FITTING ROOM	MAX.	MAXIMUM	RM.	ROOM		
CONC.	CONCRETE					S.	SOUTH		

GENERAL NOTES & ABBREVIATIONS

DEFINITIONS:

FURNISH – MEANS SUPPLY AND DELIVER TO PROJECT, FREIGHT ON BOARD TRUCK, UNLESS OTHERWISE DEFINED IN GREATER DETAIL.
INSTALL – DESCRIBES OPERATIONS AT PROJECT, FROM INSPECTION AND UNLOADING, TO COMPLETION IN PLACE, READY FOR INTENDED USE.
PROVIDE – MEANS FURNISH AND INSTALL, COMPLETE AND READY FOR INTENDED USE, UNLESS OTHERWISE DEFINED IN GREATER DETAIL.

GENERAL NOTES:

1. ITEMS NOT FOUND IN THIS MATRIX ARE TO BE PROVIDED BY THE GENERAL CONTRACTOR.
2. SEE RESPONSIBILITY MATRIX ON G0-2 FOR MORE INFORMATION.
3. HATCHED ITEMS ARE EITHER NOT IN SCOPE OF WORK, OR THEIR RESPONSIBILITY IS TO BE DETERMINED.

KEY NOTES:

1. G.C. TO COORDINATE FINAL LOCATION W/ BRAND.
2. G.C. REQUIRED TO PURCHASE FROM SUPPLIERS WITH WHOM OWNER HAS INVENTORY OR PRICING AGREEMENT.
3. G.C. RESPONSIBLE FOR PURCHASE AND DELIVERY.
4. G.C. TO COORDINATE SCHEDULE AND DELIVERY WITH SUPPLIER. STANDARD SHIPPING PROVIDED BY ATHLETA. ANY EXPEDITED SHIPPING COSTS ARE RESPONSIBILITY OF THE GENERAL CONTRACTOR.
5. ITEM DELIVERY SCHEDULED BY OWNER FOR LAST WEEK OF CONSTRUCTION.
6. G.C. TO SCRIBE TO FIT
7. REFER TO BID INSTRUCTIONS FOR VENDOR NAME AND CONTACT INFORMATION.
8. ALL FINAL EQUIPMENT WIRING AND EQUIPMENT INSTALLATION BY OTHERS
9. NOT USED
10. ROUGH-IN BY G.C.
11. FOR ROOFTOP UNITS ONLY WHEN LL PROVIDES ROOFTOP UNITS.
12. MUST BE PROVIDED BY A QUALIFIED CONTROLS CONTRACTOR. SEE PROJECT MANUAL & INSTALLATION GUIDE FOR QUALIFICATION AND SUBMITTAL REQUIREMENTS.
13. SUBMIT CATALOG DATA (INCLUDING DUCT, FITTING AND SELF SEALING GASKET) INFORMATION FOR REVIEW.
14. SEE PROJECT MANUAL & INSTALLATION GUIDE FOR DETAILED SUBMITTAL REQUIREMENTS.
15. PROVIDE SUBMITTALS TO MEP ENGINEER AND GAP ENGINEERING FOR ANY EQUIPMENT THAT IS GC FURNISHED.
16. SEE DOOR SCHEDULE FOR HARDWARE & DOOR INFORMATION
17. SEE LIGHTING SCHEDULE FOR MORE INFORMATION
18. SEE PROJECT MANUAL & INSTALLATION GUIDE FOR DETAILS, SIZES, AND REQUIREMENTS.
19. VINYL FLOORING ATTACHED TO SUBSTRATE WITH MANUFACTURER'S RECOMMENDED ADHESIVE

L: LANDLORD O: OWNER E: EXISTING G: GENERAL CONTRACTOR/SUBCONTRACTOR

KEYNOTES & DEFINITIONS

ITEM	DESCRIPTION	FURNISHED BY	INSTALLED BY	COMMENTS
NEW DEMISING WALL STUDS	STUDS FOR NEW DEMISING WALL.	L	L	
NEW DEMISING WALL GYP BOARD	GYP BOARD FOR NEW DEMISING WALL, TENANT SIDE ONLY.	L	L	SEE WALL TYPE SCHEDULE ON G0-2.2 FOR GYP BOARD TYPE AND FIRE RATING.
NEW NEUTRAL PIERS	NEW NEUTRAL PIERS AT NEW STOREFRONT.	L	L	SEE A4-0 FOR NEW NEUTRAL PIER LOCATION
SLAB LEVELING	LEVELING OF SLAB IN UNEVEN, DAMAGED OR NON-ADA COMPLIANT AREAS OF SPACE.	G	G	SEE A1-0 FOR AREAS OF SLAB TO BE LEVELED.
STUB UPS	STUB UP FOR UTILITY SERVICES INTO SPACE.	G	G	SEE A1-0 FOR LOCATION OF UTILITY STUB UPS AND TRENCHING.

SECURITY SYSTEM

EAS-1	S10-2 EAS FINS	CHECKPOINT; CUSTOM PAINTED SLIMLINE FINS – ANTENNA TO MATCH ATHLETA SATIN BLACK; MODEL #7396981 W/ HARDWARE HOOD KIT 7367100	0	0	4		
EAS-2	P10-2 EAS PEDESTAL	CHECKPOINT; CUSTOM PAINTED PEDESTAL – TO MATCH ATHLETA SATIN BLACK; MODEL #7394GT W/ SECONDARY ANTENNA 7220727	0	8	4		
EAS-3	S10-EXS EAS MOUNTING POST	CHECKPOINT; CUSTOM PAINTED FLOOR MOUNT POST – TO MATCH ATHLETA SATIN BLACK; MODEL #10109843	0	0	4		EAS-3 INCLUDES POST ONLY. EAS-1 WILL MOUNT TO EAS-3
EAS-4	F10-EVOLVE EAS IN-FLOOR RECESSED	CHECKPOINT	0	0	4		REFER TO ~~X/A4-1~~ FOR APPROVED FLOOR LEVELER ABOVE ANTENNA

PAINT (NO SUBSTITUTIONS)

P1	PAINT	SHERWIN WILLIAMS DOVER WHITE SW 6385, SOLO 100% ACRYLIC INT/EXT FLAT (A74W00051)	G	G	–	
P1-EG	PAINT	SHERWIN WILLIAMS DOVER WHITE SW 6385, SOLO 100% ACRYLIC INT/EXT EGGSHELL (A75W00051)	G	G	–	
P1-MG	PAINT	SHERWIN WILLIAMS DOVER WHITE SW 6385, MARINE GRADE, DURATION HOME LATEX SATIN (A97W01251)	G	G	–	
P1-SG	PAINT	SHERWIN WILLIAMS DOVER WHITE SW 6385, SOLO 100% ACRYLIC INT/EXT SEMI-GLOSS (A76W00051)	G	G	–	
P2	PAINT	SHERWIN WILLIAMS CEILING BRIGHT WHITE SW 7007, SOLO 100% ACRYLIC INT/EXT FLAT (A74W00051)	G	G	–	
P2-MG	PAINT	SHERWIN WILLIAMS CEILING BRIGHT WHITE SW 7007, MARINE GRADE, DURATION HOME LATEX MATTE (A96W01251)	G	G	–	
P7-SG	PAINT	SHERWIN WILLIAMS MORNING FOG SW 6258 SOLO 100% ACRYLIC INT/EXT SEMI-GLOSS (A76W00051)	G	G	–	
P7-EG	PAINT	SHERWIN WILLIAMS MORNING FOG SW 6258 SOLO 100% ACRYLIC INT/EXT EG-SHEL (A75W00051)	G	G	–	
P9-SG	PAINT	SHERWIN WILLIAMS BLACK MAGIC SW 6991 SOLO 100% ACRYLIC INT/EXT SEMI-GLOSS (A76W00051)	G	G	–	
P9-EG	PAINT	SHERWIN WILLIAMS BLACK MAGIC SW 6991 SOLO 100% ACRYLIC INT/EXT EG-SHEL (A75W00051)	G	G	–	
P12	PAINT	SHERWIN WILLIAMS SOAR SW 6799, SOLO 100% ACRYLIC INT/EXT FLAT (A74W00051)	G	G	–	
P12-MG	PAINT	SHERWIN WILLIAMS SOAR SW 6799, MARINE GRADE, DURATION HOME LATEX SATIN (A97W01251)	G	G	–	
P12-EG	PAINT	SHERWIN WILLIAMS SOAR SW 6799, SOLO 100% ACRYLIC INT/EXT EGGSHELL (A75W00051)	G	G	–	
P13-SG	PAINT	SHERWIN WILLIAMS SNOWBOUND SW 7004 SOLO 100% ACRYLIC INT/EXT SEMI-GLOSS (A76W00051)	G	G	–	
P13-EX	PAINT	SHERWIN WILLIAMS SNOWBOUND SW 7004 SOLO 100% ACRYLIC INT/EXT EG-SHEL (A75W00051)	G	G	–	
P14-EX	PAINT	SHERWIN WILLIAMS ATHLETA PURPLE SOLO 100% ACRYLIC INT/EXT EG-SHEL (A75W00051)	G	G	–	
P18	PAINT	SHERWIN WILLIAMS NETWORK GRAY SW 7073 SOLO 100% ACRYLIC INT/EXT FLAT (A74W00051)	G	G	–	
P19-SG	PAINT	SHERWIN WILLIAMS TRICORN BLACK SW 6258 SOLO 100% ACRYLIC SEMI-GLOSS (A76W00051)	G	G	–	
P-TBD-EX	PAINT	EXTERIOR GRADE PAINT TO MATCH COLOR OF (E) STOREFRONT COLOR. SUBMIT SAMPLE FOR LL APPROVAL	G	G	–	
P302	PAINT	SHERWIN WILLIAMS WATERBASED TILE CLAD EPOXY COATING, COLOR: "SAFETY RED" SW 4081 – FIELD MIX IN LOCAL STORE	G	G	–	
P303	PAINT	SHERWIN WILLIAMS WATERBASED TILE CLAD EPOXY COATING, COLOR: "SAFETY YELLOW" SW 4084 – FIELD MIX IN LOCAL STORE	G	G	–	
P304	INTUMESCENT PAINT	CARBOLINE A/D FIREFILM III	G	G	–	

NOTES: EXTENT OF PAINT TO INCLUDE AREAS BEHIND FIXTURES

SEE PROJECT MANUAL FOR SPECIFICATIONS FOR PRIMER

NEW STORE

ATHLETA

GAP INC.
CORPORATE ARCHITECTURE
1 HARRISON STREET
SAN FRANCISCO, CA 94105

STORE NO.: 7641

STORE NAME: PORTLAND

STORE LOCATION:
152 MIDDLE STREET
PORTLAND, ME 04101

PROJ. I.D.: 0000053405

PROTOTYPE DATE: 09/4/15
PROTOTYPE VERSION 4.1

CONSULTANT INFO:

PROFESSIONAL STAMP:

JOHN A. CHIPMAN No. 2089 STATE OF MAINE

ARCHITECT INFO:

ChipmanDesign Architecture Inc.
2700 S. River Road, Suite 400
Des Plaines, Illinois 60018
T 847.298.4900 F 847.298.4916

I HEREBY CERTIFY THAT THESE PLANS HAVE BEEN PREPARED IN MY OFFICE AND UNDER MY SUPERVISION AND THAT TO THE BEST OF MY KNOWLEDGE, THE SAME COMPLY WITH ALL LAWS, RULES, REGULATIONS AND ORDINANCES OF PORTLAND, ME RELATING TO STRUCTURES AND BUILDINGS.

ISSUE TYPE:
100% CD CHECKSET 5/20/16
PERMIT / BID
LL APPROVAL

DRAWN BY: NR

A&E JOB NO.: 16-5433

SHEET TITLE:
RESPONSIBILITY MATRIX, ROOM FINISH SCHEDULE, & ABBREVIATIONS

SHEET NUMBER:
G0-2.1