



FLOOR FINISH PLAN

scale: 1/8" = 1'-0"

FINISH NOTES

1. See Interior Elevations for detailed mapping of paint colors and locations of applied decorative wall panels, wainscotting, and graphics

FINISH SCHEDULE

Room #	Room Name	Floor	Base	Base Style	Walls	Remarks
100	Existing Lobby	N.I.C.	N.I.C.	N.I.C.	N.I.C.	
101	NOT USED					
101A	NOT USED					
102	Sprinkler Service Closet	EXIST.	EXIST.	EXIST.	EXIST.	
103	Bank Branch	Glazed Porc. Tile/Cork	4" Vinyl	Coved	Ptd GWB	1.
104	CSR Office	Carpet Tile	4" Vinyl	Coved	Ptd GWB	1.
105	Bank Branch (Upper)	Carpet/ Porc. Tile	4" Vinyl	Coved	Ptd GWB	1.
106	Cash Room	Carpet Tile	4" Vinyl	Coved	Ptd GWB	
107	Manager Office	Carpet Tile	4" Vinyl	Coved	Ptd GWB	1.
108	Informal Meeting Room	Carpet Tile	4" Vinyl	Coved	Ptd GWB	1.
109	Reception	Stone Tile	Stone Tile	Bullnose	Pnt GWB / Wall Cvrng	
110	Server Room	VCT Static Disip	4" Vinyl	Coved	Ptd GWB	
111	Corridor	Carpet Tile	4" Vinyl	Straight	Ptd GWB	
112	SBA Sales Mgr. Office	Carpet Tile	4" Vinyl	Straight	Ptd GWB	
113	CB President Office	Carpet Tile	4" Vinyl	Straight	Ptd GWB	
114	Retail Sales/Ops. Mgr. Office	Carpet Tile	4" Vinyl	Straight	Ptd GWB	
115	Chief Commercial Lender Office	Carpet Tile	4" Vinyl	Straight	Ptd GWB	
116	Tel/Data Closet	EXIST.	EXIST.	EXIST.	Ptd GWB	
117	Open Office Area	Carpet Tile	4" Vinyl	Straight	Ptd GWB	
118	Work Room	Resil. Tile	4" Vinyl	Coved	Ptd GWB	
119	Work Room	Resil. Tile	4" Vinyl	Coved	Ptd GWB	
120	Secure File Room	VCT	4" Vinyl	Coved	Ptd GWB	
121	Commercial Lender 1 Office	Carpet Tile	4" Vinyl	Straight	Ptd GWB	
122	Mother Room	Carpet Tile	4" Vinyl	Straight	Ptd GWB	
123	Storage Room	VCT	4" Vinyl	Coved	Ptd GWB	
124	Electrical Room	EXIST.	EXIST.	EXIST.	EXIST.	
125	Kitchen	Resil. Tile	4" Vinyl	Coved	Ptd GWB	
126	Commercial Lender 2 Office	Carpet Tile	4" Vinyl	Straight	Ptd GWB	
127	Human Resources Office	Carpet Tile	4" Vinyl	Straight	Ptd GWB	
128	Cafe	Resil. Tile	4" Vinyl	Coved	Ptd GWB	
129	Toilet Room	Stone Tile	Stone Tile	Bullnose	Ptd GWB	
130	Coats	VCT	4" Vinyl	Coved	Ptd GWB	
131	Lobby	Carpet Tile	4" Vinyl	Straight	Ptd GWB	
132	Corridor	Carpet Tile	4" Vinyl	Straight	Ptd GWB	
133	Coats	VCT	4" Vinyl	Coved	Ptd GWB	
134	Small Conference Room	Carpet Tile	4" Vinyl	Straight	Ptd GWB	
135	Men's Toilet Room	Glazed Porc. Tile	Glazed Porc. Tile	Bullnose	Ptd GWB	
136	Women's Toilet Room	Glazed Porc. Tile	Glazed Porc. Tile	Bullnose	Ptd GWB	
137	Mortgage Lender 2 Office	Carpet Tile	4" Vinyl	Straight	Ptd GWB	
138	Mortgage Lender 1 Office	Carpet Tile	4" Vinyl	Straight	Ptd GWB	
139	Swing Space 1 Office	Carpet Tile	4" Vinyl	Straight	Ptd GWB	
140	Swing Space 2 Office	Carpet Tile	4" Vinyl	Straight	Ptd GWB	
141	Swing Space 3 Office	Carpet Tile	4" Vinyl	Straight	Ptd GWB	
142	Conference Room	Carpet Tile	4" Vinyl	Straight	Ptd GWB	
143	Conference Room	Carpet Tile	4" Vinyl	Straight	Ptd GWB	
144	A/V Closet	VCT Static Disip	4" Vinyl	Coved	Ptd GWB	
145	ATM Closet	VCT Static Disip	4" Vinyl	Coved	Ptd GWB	
146	ATM Vestibule	Entry Carpet Tile	4" Vinyl	Straight	Ptd GWB	1.
147	Stair/Landing	Broadloom Carpet	4" Vinyl	Straight	Ptd GWB	

FLOORING LEGEND

- CARPET TILE - TYPE 1: Mannington Commercial - 'BARK' Color: #8212 - Cedar / Vinyl Base: Johnsonite #283 Toast - 6" Straight Profile - No cove
- CARPET TILE - TYPE 2: Mannington Commercial - 'SQUAREBERRY' Color: #8212 - Cedar / Vinyl Base: Johnsonite #283 Toast - 6" Straight Profile - No cove
- CARPET TILE - TYPE 3: Tandus Carpet Tile - 'MONUMENTO' #03588 Color: #79013- Green Scheme / Vinyl Base Johnsonite #283 Toast - 4" Straight Profile-No cove
- ENTRY CARPET TILE - TYPE 1: Mohawk Group - 'FIRST STEP' Color: #00438 - Windswept / Vinyl Base Johnsonite #283 Toast - 4" Straight Profile-No cove
- BROADLOOM CARPET - TYPE 1: Mannington Commercial - 'BARK' Color: #8212 - Cedar / Vinyl Base: Johnsonite #283 Toast - 6" Straight Profile - No cove
- RESILIENT VINYL TILE: Mannington Commercial - 'ASSURANCE II' 18" Square Tile - Color: #16307 - Putty / Vinyl Base: Johnsonite #283 Toast - 6" Coved Profile
- VINYL COMPOSITION TILE 1: - Mannington Commercial - 'PROGRESSIONS' 12" Square Tile - Color: #55129 - Putty / Vinyl Base: Johnsonite #283 Toast - 6" Coved Profile
- VINYL COMPOSITION TILE 2: (Static Dissipative) - Roppe - 'ESD Vinyl' 12" Square Tile - Color: #751 - Haze Gray / Vinyl Base: Johnsonite #195 Ash - 6" Coved Profile
- CORK TILE 1: Duro-Design 'MARMOL MAPLE' Cork Tile
- GLAZED PORCELAIN TILE 1 - Florida Tile - 'TIDES' 12" x 24" Tile - Color: #28115 - Marine Fog / Matching 3" x 24" Bullnose Base / Grout: Mapei UltraColor Grout #02 Pewter
- STONE TILE
- GLAZED PORCELAIN TILE 2: - Best Tile - 'DURBAN' 8" x 48" Tile - Color: #256272 / Grout: Laticrete PermaColor Grout #89 Smoke Gray



5 Milk Street
Portland, Maine 04101
207 774 4811
www.wintonscott.com



Branding / Bank Branch Interior Design:
THE ELEMENT GROUP

125 Brewery Lane
Suite #9
Portsmouth, NH 03801
T. 603.319.9561

Structural Engineering:
STRUCTURAL INTEGRITY ENGINEERS

77 Oak Street
Portland, ME 04101
T. 207.774.4614

HVAC & plumbing Engineering:
MECHANICAL SYSTEMS ENGINEERS

Royal River Center, Unit 10
10 Forest Falls Drive
Yarmouth, ME 04096
T. 207.846.1441

Electrical Engineering:
SWIFT CURRENT ENGINEERING

Royal River Center, Unit 4B
10 Forest Falls Drive
Yarmouth, ME 04096
T. 207.847.9280



Portland Branch

27 Pearl Street
1st Floor Tenant Space
Portland, Maine

FINAL CONSTRUCTION SET

MARCH 4, 2015

FLOOR FINISH PLAN & FINISH SCHEDULE

Scale: As Noted

A1.3