



**1** EXISTING CONDITIONS SITE PLAN  
scale: 1/16" = 1'-0"



**2** PROPOSED CONDITIONS SITE PLAN  
scale: 1/8" = 1'-0"

- REINFORCED 6" SLAB ON GRADE :
- #3 BARS AT 12" O.C. EA WAY
  - THICKEN SLAB TO 9" AT FACE OF EXISTING BLDG. FOUNDATION WALL & PIN W/ #4 BARS @ 16" O.C.
  - THICKEN SLAB TO 12" AT PERIMETER EDGES
  - 2" RIGID INSULATION UNDER ENTIRE SLAB
  - SET SLAB ON 3" OF COMPACTED DRAINAGE FILL.
  - PROVIDE BROOM FINISH W/ TROWELED CONTROL JOINTS



**3** TYPICAL CONCRETE SECTION DETAIL  
scale: 3" = 1'-0"



Branding / Bank Branch Interior Design:  
**THE ELEMENT GROUP**

125 Brewery Lane  
Suite #9  
Portsmouth, NH 03801  
T. 603.319.8951

Structural Engineering:  
**STRUCTURAL INTEGRITY ENGINEERS**

77 Oak Street  
Portland, ME 04101  
T. 207.774.4614

HVAC & plumbing Engineering:  
**MECHANICAL SYSTEMS ENGINEERS**

Royal River Center, Unit 10  
10 Forest Falls Drive  
Yarmouth, ME 04096  
T. 207.846.1441

Electrical Engineering:  
**SWIFT CURRENT ENGINEERING**

Royal River Center, Unit 4B  
10 Forest Falls Drive  
Yarmouth, ME 04096  
T. 207.847.9280