# EATON PEABODY

100 MIDDLE STREET, SECOND FLOOR

PORTLAND, MAINE

## DRAWING INDEX



| | | | 11/29/16 PERMITTING SET |
|---|---|---|---|
| GENERAL | G101 | TITLE SHEET & DRAWING INDEX | ● |
| | G102 | CODE REVIEW | ● |
| SITE/CIVIL | | | |
| LANDSCAPING | | | |
| STRUCTURAL | S100 | THIRD FLOOR FRAMING PLAN | ● |
| | S200 | SECTIONS, DETAILS AND GENERAL NOTES | ● |
| ARCHITECTURAL | D100 | SECOND FLOOR DEMOLITION PLAN/NOTES | ● |
| | A100 | SECOND FLOOR PLAN / PARTITION TYPES | ● |
| | A200 | EXISTING SECOND FLOOR POWER PLAN–LEGEND | ● |
| | A201 | PROPOSED SECOND FLOOR POWER PLAN–LEGEND | ● |
| | A300 | EXISTING REFLECTED CEILING PLAN – LEGEND | ● |
| | A301 | REFLECTED CEILING PLAN – LEGEND | ● |
| | A800 | FINISH LEGEND / INTERIOR ELEVATIONS DOOR SCHEDULE/DOOR & FRAME TYPES | ● |
| MECH/ PLUMBING | | | |
| ELECTRICAL | | | |



## ABBREVIATIONS

| | | | | | |
|---|---|---|---|---|---|
| ALUM OR AL | ALUMINUM | GALV | GALVANIZED | S | SOUTH |
| AWP | ACOUSTICAL WALL PANEL | GB | GRAB BARS | SC | SHOWER CURTAIN |
| ACT | ACOUSTICAL CEILING TILE | GC | GENERAL CONTRACTOR | SD | SOAP DISPENSER |
| BIT | BITUMINOUS | GWB | GYPSUM WALL BOARD | SCHED | SCHEDULE |
| BM | BENCH MARK | HC | HANDICAP | SECT | SECTION |
| BOT | BOTTOM | HD WD | HARDWOOD | SHT | SHEET |
| BRG | BEARING | HDR | HEADER | SIM | SIMILAR |
| BRK | BRICK | HDWE | HARDWARE | SND | SANITARY NAPKIN DISPOSAL |
| C | CARPET | HM | HOLLOW METAL | SQ | SQUARE |
| CAB | CABINET | HORZ | HORIZONTAL | SSS | SYNTHETIC SPORTS SURFACE |
| CB | CHALK BOARD | HT | HEIGHT | STD | STANDARD |
| CC | CENTER TO CENTER | ID | INSIDE DIAMETER | STL | STEEL |
| CH | CONCRETE HARDENER | IF | INSIDE FACE | STRUCT | STRUCTURAL |
| CJ | CONTROL JOINT | IN | INCHES | SV | SHEET VINYL |
| CL | CENTER LINE | INSUL | INSULATION | T | TEMPERED (GLASS) |
| CLG | CEILING | INT | INTERIOR | TB | TACK BOARD |
| CMU | CONCRETE MASONRY UNITS | LOC | LOCATION | THK | THICKNESS |
| CONC | CONCRETE | M | MARBLE | TO | TOP OF |
| CONT | CONTINUOUS | MAS | MASONRY | TOB | TOP OF BEAM |
| CONST | CONSTRUCTION | MAX | MAXIMUM | TOM | TOP OF MASONRY |
| CONTR | CONTRACTOR | MB | MARKER BOARD | TOW | TOP OF WALL |
| CT | CERAMIC TILE | MECH | MECHANICAL | TP | TOILET PAPER DISPENSER |
| DBL | DOUBLE | MFGR | MANUFACTURER | TYP | TYPICAL |
| DF | DRINKING FOUNTAIN | MIN | MINIMUM | UNO | UNLESS NOTED OTHERWISE |
| DIA | DIAMETER | MISC | MISCELLANEOUS | VB | VAPOR BARRIER |
| DIM | DIMENSION | MO | MASONRY OPENING | VCT | VINYL COMPOSITION TILE |
| DNA | DOES NOT APPLY | MR | MOP RECEPTOR | VERT | VERTICAL |
| DTL | DETAIL | MRGB | MOISTURE RESISTANT GYPSUM BOARD | VWC | VINYL WALL COVERING |
| DWG | DRAWING | | | W | WEST |
| E | EAST | MTL | METAL | W/ | WITH |
| EA | EACH | N | NORTH | WC | WATER CLOSET |
| EF | EACH FACE | NA | NOT APPLICABLE | WD | WOOD |
| EJ | EXPANSION JOINT | NIC | NOT IN CONTACT | | |
| EL | ELEVATION | NO | NUMBER | | |
| ELEC | ELECTRICAL | NOM | NOMINAL | | |
| ELEV | ELEVATOR | NTS | NOT TO SCALE | | |
| EMHO | ELECTROMAGNETIC HOLD OPEN | OA | OVERALL | | |
| EQ | EQUAL | OC | ON CENTER | | |
| EW | EACH WAY | OD | OUTSIDE DIAMETER | | |
| EWC | ELECTRIC WATER COOLER | OPNG | OPENING | | |
| EXIT OR (E) | EXISTING | OPP | OPPOSITE | | |
| EXP | EXPANSION | OF | OUTSIDE FACE | | |
| EXT | EXTERIOR | P | PAINT | | |
| FD | FLOOR DRAIN | PTD | PAINTED | | |
| FDN | FOUNDATION | PL | PLATE | | |
| FE | FIRE EXTINGUISHER | PLY WD | PLYWOOD | | |
| FFE | FINISH FLOOR ELEVATION | PNL | PANEL | | |
| FIN | FINISH | P.A. | PRESSURE TREATED | | |
| FIN FL OR FF | FINISH FLOOR | PT & D | PAPER TOWEL AND WASTE DISPENSER | | |
| FIN GR | FINISH GRADE | | | | |
| FL | FLOOR | PTN | PARTITION | | |
| FR | FIRE RATING | RD | ROOF DRAIN | | |
| FRMG | FRAMING | RE | REFER | | |
| FT | FEET (FOOT) | REF | REFRIGERATOR | | |
| FV | FIELD VERIFY | REINF | REINFORCED | | |
| FWC | FABRIC WALL COVERING | REQD | REQUIRED | | |
| G | GRANITE | RM | ROOM | | |
| GA | GAUGE | RO | ROUGH OPENING | | |

## LEGEND

- BUILDING SETION MARKER
- CEILING TAG (ACT1 / 8'-0")
- COLUMN CENTER LINE
- DETAIL MARKER
- DOOR TAG (101)
- EXTERIOR ELEVATION
- INTERIOR ELEVATION (A1 / A920)
- PLANT TAG (200 — HPD)
- REVISION CLOUD WITH TAG (1)
- ROOM TAG (ROOM / A101)
- SECTION MARKER
- WALL TYPE (W1)
- WINDOW TAG (A)

## GENERAL NOTES

1. THE GENERAL CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS, AND REPORT ANY DISCREPANCIES TO THE ARCHITECT. CONTRACTOR SHALL PROCEED WITH THE WORK ONLY AFTER DISCREPANCY HAS BEEN RESOLVED WITH THE ARCHITECT.

2. DO NOT ALTER OR PENETRATE ANY EXISTING STRUCTURAL ELEMENTS, EXTERIOR WALL COMPONENTS, OR FIRE RATED WALLS

3. THE LOCATIONS OF DOORS NOT DIMENSIONED SHALL BE 4 INCHES FROM ADJACENT WALL.

4. THE BUILDING SHALL BE CONSTRUCTED TO CONFORM WITH ALL APPLICABLE CODES INCLUDING, BUT NOT LIMITED TO, THE LATEST EDITIONS OF IBC 2009, NFPA 101, & ANSI.

5. ALL WOOD IN CONTACT WITH CONCRETE SHALL BE PRESSURE PRESERVATIVE TREATED & ALL CONNECTIONS TO BE STAINLESS STEEL.

6. CONTRACTOR SHALL WORK FROM GIVEN DIMENSIONS AND LARGE SCALE DETAILS ONLY. DO NOT SCALE THE DRAWINGS.

7. REFER TO OUTLINE SPECIFICATION FOR ADDITIONAL INFORMATION AND SCOPE OF WORK.

8. EXISTING BUILDING COMPONENTS WHICH ARE AFFECTED BY NEW WORK AND DEMOLITION, OR WHICH MAY BE DAMAGED BY THE CONTRACTOR OR ANY SUBCONTRACTORS SHALL BE REPLACED OR RESTORED TO ORIGINAL CONDITION AND COLOR BY METHODS DESCRIBED IN THIS CONTRACT OR AS APPROVED BY THE ARCHITECT. THE GENERAL CONTRACTOR SHALL SEAL, PATCH, SKIM COAT AND FILL ANY FLOOR AND/OR WALL PENETRATIONS DUE TO DEMOLITION/CONSTRUCTION.

9. INSTALL BLOCKING BEHIND ALL SURFACE APPLIED FIXTURES, TRIM, CABINETS, COUNTER TOPS, AND GRAB BARS WHEN MOUNTED ON STUD WALLS.

10. NOT USED

11. CONTRACTOR SHALL VERIFY SIZE AND LOCATION OF EXISTING MECHANICAL AND PLUMBING ELEMENTS. CONTRACTOR SHALL RENOVATE EXISTING ALARM SYSTEM TO MAINTAIN CONFORMANCE TO NFPA 13 & 101. CONTRACTOR SHALL VERIFY SIZE & LOCATION OF ALL ELECTRICAL SERVICES AND EQUIPMENT.

12. INSTALL MOISTURE RESISTANT GYPSUM BOARD IN LAVATORIES, JANITOR CLOSETS, AND ALL OTHER HIGH HUMIDITY AREAS.

13. FINISHES: FINISHES OTHER THAN THE STANDARD FINISHES ARE ALL INDICATED ON THE DRAWINGS, CEILING FINISHES ARE SHOWN ON THE REFLECTED CEILING PLANS AND ALL OTHER FINISHES ARE SHOWN ON THE INTERIOR FINISH LEGEND AND SCHEDULE AND/OR INTERIOR ELEVATIONS. FINISHES INDICATED FOR A PARTICULAR ROOM OR SPACE ARE APPLICABLE FOR THE ENTIRE ROOM OR SPACE, UNLESS OTHERWISE NOTED.

14. ALL EXPOSED SURFACES ARE TO BE PAINTED, WHETHER OR NOT INDICATED ON THE DRAWINGS, EXCEPT AS FOLLOWS: WHERE SPECIAL COATINGS ARE INDICATED; PREFINISHED ITEMS, CONCEALED SURFACES, OPERATING PARTS, AND LABELS. IF PREFINISHED, PAINTING THE FOLLOWING: EXPOSED MECHANICAL DUCTWORK, WALL DIFFUSERS, GRILLES AND LOUVERS, ROOF TOP MECHANICAL EQUIPMENT, AND SPEAKER GRILLES. FINISHED METAL SURFACES, EXCEPT AS LISTED ABOVE. SEE SPECIFICATIONS ON DRAWINGS IDENTIFYING THE TYPES OF PAINTS AND SPECIALTY COATINGS TO BE USED IN ACCORDANCE WITH MATERIAL BEING PAINTED OR COATED.

15. BUILDING INSULATION: PROVIDE AS INDICATED ON WALL DETAILS AND IN ACCORDANCE WITH PARTITION TYPES, WHETHER OR NOT SHOWN IN DETAILS AND DRAWINGS. FOR DRAWING CLARITY, INSULATION MAY NOT BE SHOWN, EVEN IF IT IS PROVIDED.

16. CONTRACTOR SHALL SUBMIT SAMPLES OF ALL INTERIOR FINISHES FOR ARCHITECT'S REVIEW.

17. THE DESIGN AND INSTALLATION OF THE HVAC AND PLUMBING SYSTEMS, ELECTRICAL AND FIRE PROTECTION SYSTEMS SHALL BE PROVIDED THROUGH A DESIGN/BUILD CONTRACT UNDER THE BUILDING MANAGER.

18. GENERAL CONTRACTOR SHALL SUPPLY POWER AND COORDINATION TO THE TENANT SUPPLIED SYSTEMS FURNITURE.

19. GENERAL CONTRACTOR SHALL SUPPLY POWER AND CONDUITS WITH PULL-STRINGS FOR DATA AND TELEPHONE TO ALL POWER POLES FOR THE OWNER SUPPLIED WORKSTATIONS. THE DESIGN AND INSTALLATION OF THE DATA AND TELEPHONE SYSTEMS SHALL BE THE RESPONSIBILITY OF THE TENANT. GENERAL CONTRACTOR TO PROVIDE CONDUIT WITH PULL-STRINGS TO ALL LOCATIONS RECEIVING DATA AND TELEPHONE.

## SITE LOCATION MAP

## ALTERNATES & ALLOWANCES:

ALTERNATE 1: PROVIDE AN OPTION FOR CARPET TILES TO REPLACE THE BUILDING STANDARD BROADLOOM CARPET. CARPET TILES TO BE PRICED AT $38.00/YARD.

ALTERNATE 2: PROVIDE 1 x 3 PAINTED FLAT STOCK TRIM AT ALL EXISTING SIDELITES AND DOORS.

ALTERNATE 3: OPERABLE PARTITION AND STRUCTURAL STEEL SUPPORT IN BOARDROOM – REFER TO OUTLINE SPECIFICATION FOR INFORMATION AND S100, S200 FOR STRUCTURAL INFORMATION.

ALTERNATE 4: SWITCH OUT ALL EXISTING PARABOLIC LIGHTS TO LED

ALLOWANCE: CUSTOM RECEPTION DESK – $7,000.00 ALLOWANCE

UNIT PRICE 1: DUPLEX WALL OUTLET

UNIT PRICE 2:
A. 2x4 PARABOLIC LIGHT FIXTURE
B. 2x2 PARABOLIC LIGHT FIXTURE
C. 2x4 DIRECT/INDIRECT LIGHT FIXTURE
D. 2x2 LED LIGHT FIXTURE
E. NEW LED RECESSED DOWN LIGHT

## PROJECT DIRECTORY


BUILDING MANAGER:
CBRE BOULOS ASSET MANAGEMENT
ONE CANAL PLAZA
PORTLAND, ME 04101

TENANT:
EATON PEABODY

ARCHITECT:
GAWRON TURGEON ARCHITECTS
29 BLACK POINT ROAD
SCARBOROUGH, MAINE 04074
207-883-6307

CONTRACTOR:
TBD

STRUCTURAL ENGINEER:
M2 STRUCTURAL ENGINEERING
23 THORNBURY WAY WINDHAM, ME 04062
207-892-0983

LANDSCAPE ARCHITECT:
N/A

SITE/CIVIL ENGINEER:
N/A

MECHANICAL ENGINEER:
DESIGN BUILD BY BUILDING MANAGER

ELECTRICAL ENGINEER:
DESIGN BUILD BY BUILDING MANAGER


LICENSED ARCHITECT STANLEY W. GAWRON 1145 STATE OF MAINE


29 BLACK POINT ROAD
SCARBOROUGH, MAINE 04074
207-883-6307
WWW.GAWRONTURGEON.COM
GAWRON TURGEON ARCHITECTS, P.C.


EATON PEABODY
100 MIDDLE STREET
PORTLAND, MAINE

REVISIONS

| # | DATE | DESCRIPTION |
|---|---|---|
| | | |

| | |
|---|---|
| DATE | 11-29-16 |
| PROJECT # | 080216 |
| DRAWN BY: | DLP |
| CHECKED BY: | SWG |
| DRAWING SCALE | N.A. |

SHEET TITLE

TITLE SHEET & DRAWING INDEX

G101


(C) COPYRIGHT 1985-2008
REPRODUCTION OR REUSE OF THIS DOCUMENT WITHOUT WRITTEN PERMISSION OF GAWRON TURGEON ARCHITECTS IS PROHIBITED