Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 07/07/17

EST3 Addressable Fire Alarm System Addition
2nd Fl Renovation - 100 Middle St
Portland, Maine

System Narrative

In the event of an alarm from an actuated device, the following shall occur:

(Devices reporting as alarm: Manual Station, Smoke Detector, Heat Detector, and Sprinkler Waterflow,)

1) Notify Portland Fire Department via existing means

2) Activate existing evacuation sequence.

3) Annunciate audibly, visually, and in plain English the active initiating device at the Fire Alarm Control Panel

4) If smoke detector is designated an elevator device, activate relays for elevator recall

5) Activate all applicable existing building relays

In the event of a supervisory condition from an actuated device, the following shall occur:

(Devices reporting as supervisory: Sprinkler Tamper Switches)

1) Notify Portland Fire Department via existing means

2) Annunciate audibly, visually, and in plain English the active initiating device at the Fire Alarm Control Panel

In the event of a system trouble report, the following shall occur:

1) Annunciate audibly, visually, and in plain English the active initiating device at the Fire Alarm Control Panel