

The Olympia Companies Office Renovation - 7 Custom House St. 5th floor

	IBC 2009		NFPA 101 2009	
Sprinklers		NFPA 13		NFPA 13
Occupant Load	T 1004.1.1	Business (B) Tenant 2 - 4,813 sf (100 per occ) = 49 occupants	7.3.1.2	B 4,813 sf (100 per occ) = 49 occupants
Use Group(s)	304.1	Business (B)	38	Business
Construction Type	T 503	3B - Mixed Combustible unprotected		III (000) Mixed-combustible unprotected
Distances to Exits	1016.1	Business - 300' Travel Distance to exits (with sprinklers)	38.2.6.3	300' Travel Distance to exits with Sprinklers
	1014.3	B - 100' Common Path of Travel with sprinkler	38.2.5.3.1	100' Common Path of Travel with sprinkler
		Maximum Common Path of Travel proposed = 92'-6"		