NOTES:

1.) ALL NEW SOFFITS AND WALLS TO BE ACOUSTICALLY INSULATED, TYPICAL.

2.) CONTRACTOR TO CONFIRM HEIGHTS OF SOFFITS WITH GLASS INSTALLER WHERE APPLICABLE

3.) FURNITURE LAYOUT SHOWN FOR GRAPHIC PURPOSES ONLY

GRAPHIC DEPICTION (SECTION)	DESCRIPTION
	- NEW METAL FRAMED WALL SYSTEM (WITH 2" DEEP LEG TOP TRACK) FASTENED THROUGH TO CONCRETE CEILING DECK - CONTRACTOR TO CONFIRM HEIGHT OF SOFFIT WITH GLASS INSTALLER - NEW 1" BOTTOM RAIL WITH HIDDEN TOP RAIL FRAMELESS GLASS SYSTEM

TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING
G1	N/A	N/A	N/A	N/A

GRAPHIC DEPICTION (SECTION)	DESCRIPTION
	- NEW METAL FRAMED WALL SYSTEM TO TERMINATE AT BOTTOM OF EXISTING CEILING DECK - ⅝" TYPE 'X' GWB - 3⅝" METAL STUDS AT 16" O.C. - 3½" SOUND BATT INSULATION - ⅝" TYPE 'X' GWB

TYPE	FIRE RATING	UL NUMBER	STC RATING	IIC RATING
1A	1 HOUR			

1 PROPOSED FLOOR PLAN
1/4" = 1'-0"

REGISTERED ARCHITECT
RYAN J. SENATORE
No. 3322
STATE OF MAINE

© 2016 RYAN SENATORE ARCHITECTURE

THE OLYMPIA COMPANIES

7 CUSTOM HOUSE STREET, 5TH FLOOR
PORTLAND, MAINE

RSA
RYAN SENATORE
ARCHITECTURE
565 CONGRESS STREET
PORTLAND, MAINE 04101
207-650-6414
senatorearchitecture.com

CONSULTANTS:

REVISIONS:

DATE:	07 SEPTEMBER 2016
PROJECT No.	1640
DRAWN BY:	RRT
CHECKED BY:	RJS
SCALE:	AS NOTED

SHEET TITLE:

PROPOSED FLOOR PLAN

A1-1