Project # 300506 July 11, 2006 Issued for Permit

ARCHITECTURE

SECTION 01150

PRE INSTALLATION CRITERIA

1.0 GENERAL

1.1. "Pre-Installation" and / or "Pre-Placement" meetings shall be held, at the project site, prior to the installation of work which require coordination, special installation, testing and / or controlled proceedures.

These meetings shall include, but not necessarily be limited to the following:

- A. **PRE-START-UP MEETING**
- $B. \hspace{0.5cm} Pre-Site-Demolition / \hspace{0.1cm} Clearing \hspace{0.1cm} / \hspace{0.1cm} Excavation \hspace{0.1cm} / \hspace{0.1cm} Grading \hspace{0.1cm} / \hspace{0.1cm} etc.$
- C. Pre-foundation placement
- D. Pre-slab placement
 - All footing excavation shall be inspected prior to placement.
- Pre-placement Sitework Concrete
 All below slab excavations, vapor barriers, and fill shall be inspected as described in 01010 prior to placement of Concrete.
- F. Pre-Framing Steel Frame
- G. A Pre skin meeting to coordinate the entire skin construction with all related trades including, but not limited to, framing, prefabricated panels, masonry, siding, sealants, windows, MEP/FP (penetrations), etc. Refer to Section 01050 .
- H. Pre-Pre-cast
- I. Pre Masonry
- J. Pre-Insulation
- K. Pre Gypsum Wall Systems
- L. Pre- Plumbing / Mechanical / Electrical / Fire Protection [May be one or several meetings.]
- M. Pre-Roofing
 N. Pre-Finishing
 [All roofing trades shingles, metal, etc.]
 [drywall, painter, VWC, specialty finishes, etc.]
- O. Pre-Landscaping [sidewalks, irrigation, utilities, etc.]
- 1.2. These meetings shall include the following individuals and others as may be necessary.
 - A. The attendees shall include:

General Contractor Project Manager and Superintendent

Subcontractor (s) Sub Owner and Foreman

Material Supplier Supplier Owner

Material Manufacturer Technical Representative

Designer Structural Engineer and/or Architect

Design / Build Systems Subcontractor Engineer(s)

Testing Agency Engineer with training in the specific trade.

Owner Representative (Optional)

- B. See individual Specification sections for more specifics.
- 1.3. The Pre-meetings shall be conducted and minutes shall be maintained by the General Contractor and distributed to all parties within 3 business days, or prior to work commencing (relative to the pre-meeting), whichever is earlier. These minutes shall serve as the installation guide for the trade.

END OF SECTION