

ARCHITECTURE

SECTION 09680

CARPET

PART 1 - GENERAL

1.1 SECTION REQUIREMENTS

- A. Submittals: Product Data and color Samples.
- B. Comply with CRI 104, Section 6, "Site Conditions."
- C. Extra Materials: Deliver to Owner full-width carpet equal to 5 percent of each type and color carpet installed, packaged with protective covering for storage.

PART 2 - PRODUCTS

2.1 CARPETS:

- A. CPT-1: Office Space: Final carpet selection to be determined. Contractor to carry a materials allowance of \$16.00 / sq. yd.
 - 1. Allow for a waste factor based on a 2 foot pattern match.
 - 2. Allow for a 2% owner stock for future repairs and replacement.
- B. Critical Radiant Flux Classification: Class I, not less than 0.45 w/sq. cm per ASTM E 648.

2.2 Transition strips: provide vinyl strips at edges of carpeting exposed to traffic.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Comply with CRI 104, Section 8, "Direct Glue-Down." Section 11, "Stretch-in Utilizing Tackless Strip."
- B. Install tackless strip with fastener approved by manufacturer for installation in concrete sub-floor.
- C. Maintain uniformity of carpet direction and lay of pile. At doorways, center seams under door in closed position. Bind or seal cut edges as recommended by carpet manufacturer. Install pattern parallel to walls and borders.

END OF SECTION 09680