

**ARCHITECTURE**  
**SECTION 09950**  
**WALL COVERINGS**

**PART 1 - GENERAL**

1.1. CONTENTS

- A. Vinyl Wall Covering - Furnished and installed by Contractor.
- B. Prime Coat on Walls by painting SECTION 09900.
- C. Adhesives and Cleaning of Adjacent Surfaces
- D. All Accessories for Complete Installation

1.2. QUALITY ASSURANCE

- A. Contractor is responsible for receiving and handling on site and installing wall covering material.
- B. Provide strippable adhesive and primer for all wall covering.
- C. Contractor shall provide wall covering quantity take-offs.
- D. Single Source Responsibility: Provide adhesives and primers produced by the same manufacturer.

**PART 2 - PRODUCTS**

2.1. WALLCOVERING

- A. Performance Criteria - Wallcovering: Type II, 20oz./ly, 52in. or 54in. width, Osaburg Fabric, Flame Spread 25, Smoke Density Factor 15.  
Confirm that materials provided bear UL label and marking, indicating the fire hazard classification of the wall covering as determined by ASTM E84 - Class A.
- B. Confirm with Owner, when verifying material quantities that all Vinyl Wall Coverings shall be mildew resistant fabric backed products equal to U.S. Vinyl Namil-Trac synthetic woven fiber which will not provide any food source to fungus or mildews or molds. Vinyl Wall Coverings shall also be furnished with micro-venting.

2.2. PRIMER/ADHESIVE

- A. Manufacturer's recommended adhesive, primer and sealer manufactured expressly for use with the selected wall covering. Provide materials that contain mildew inhibitors that are non-staining to the wall covering.
- B. Alternative Manufacturers:
  - Fred Smith Adhesives, Inc. (201-736-7979)
    - Primer: "22005 Sealing Primer"
    - Adhesive: "18105 Tinted Strippable"
  - Roman Adhesives, Inc. (800-488-6117)
    - Primer: "UltraPrime 977"
    - Adhesive: "Ultra Pro 880", or, if pasting machine is used, "Clear Strippable Pro 870".

**PART 3 - EXECUTION**

- A. Performance Criteria - General: Comply with wall-coverings manufacturers' written installation instructions applicable to products and applications indicated, except where more stringent requirements apply.
- B. All walls shall be primed prior to installing wall covering.

**END OF SECTION**