NOTES:

1. THIS PLAN REPRESENTS A PRELIMINARY LAYOUT OF THE CONDUIT AND UNDERGROUND VAULT LOCATIONS. FINAL ELECTRICAL SERVICE DRAWINGS TO BE PROVIDED BY CMP.
2. PRIMARY VOLTAGE CABLE WILL BE 500RCM CU 15kV URD & ⅔AL 15kV URD
3. ALL CONSTRUCTION TO BE IN COMPLIANCE WITH CMP'S CONSTRUCTION STANDARDS AND THE LATEST EDITION OF THE NATIONAL ELECTRICAL SAFETY CODE.
4. CONDUITS SHALL BE PROPERLY PITCHED TO DRAIN INTO TRANSFORMER FOUNDATIONS, MANHOLES OR SPLICE BOXES. THREE INCHES PER 100 FEET MINIMUM SLOPE.
5. INSTALL PULLING LINE IN EACH CONDUIT.
6. THE CONTRACTOR IS REQUIRED TO NOTIFY CMP BY CALLING THE LINE SUPERVISOR AT 791-1020 AT LEAST 72 HOURS BEFORE TRENCH EXCAVATION BEGINS.

N/F
OLYMPIA EQUITY
INVESTORS IV, LLC
029- -K-001

N/F
OLYMPIA EQUITY
INVESTORS IV B, LLC
029- -K-001

N/F
EAST BROWN COW LIMITED
11835/88
029- -K-002

N/F
OLYMPIA EQUITY
INVESTORS IV P, LLC
029- -K-005

N/F
25 PEARL MHR LLC
029- -E-009

N/F
JACK I NOVICK &
ROSE NOVICK
029- -E-010

N/F
SAMUEL L NOVICK
029- -E-012

NORTH

EXISTING 38Y MANHOLE REMOVE TOP AND REPLACE WITH VAULT GRATING TOP

EXISTING 6'x12' MANHOLE

6-4" CONDUITS CONCRETE ENCASED

2-4" CONDUITS

4-6" CONDUITS CONCRETE ENCASED

1-2" CONDUIT

4'x4' HAND HOLE WITH 32" COVER

1-2" CONDUIT TO RISER

BRICK SIDEWALK

BIT. WALK

WOOD DECK

BRICK PAVERS

OVERHEAD AIR CONDITIONING UNITS

FORE STREET RESTAURANT/ STANDARD BAKERY

LOADING AREA

GAS METER

GAS PIPE

TELEPHONE MH

DOUBLE YELLOW LINE

GRAPHIC SCALE

(IN FEET)
1 inch = 10 ft.

BID SET

REV	DATE	DESCRIPTION
1	06.02.06	RELEASED FOR BIDS

REVISIONS

STATE OF MAINE CHRISTOPHER J. OSTERRIEDER 9106 REGISTERED PROFESSIONAL ENGINEER

P.E. CHRISTOPHER OSTERRIEDER
LIC. #9106

PROJECT
CUSTOM HOUSE SQUARE OFFICE BUILDING

SHEET TITLE
ELECTRICAL PLAN

CLIENT
OLYMPIA EQUITY INVESTORS, IVB

DeLUCA-HOFFMAN ASSOCIATES, INC.
778 MAIN STREET, SUITE 8
SOUTH PORTLAND, ME 04106
207.775.1121
WWW.DELUCAHOFFMAN.COM

DRAWN:	ECJ	DATE:	NOV. 2005
DESIGNED:	CJO	SCALE:	1"=10'
CHECKED:	CJO	JOB NO.	2581
FILE NAME:	2581-SP		
SHEET	C-4A		

SCREENSHARED

G:\2581\dwg\BID SET\2581-SP-MOVE-VAULT.dwg, ELECTRICAL, 6/1/2006 5:36:30 PM, jjordan