



**NOTES:**  
 Double-face, non-illuminated shingle-type sign, to suspend from existing support mast; sign to consist of 1/2" MDO sign panels with 3/8" PVC copy / logo, and smalted backgrounds, 4" diameter cove molding, and copper drip cap, all mounted on 1" square tube frame.  
 Copy to be painted white.  
 Logo to be painted red PMS #1795C.  
 Face backgrounds to be black sand smalted finish.  
 Cove molding to be white.  
 Edges of sign to be painted black.

NOTE: due to printer limitations, colors shown may not exactly match specified. Refer to material charts for true colors.



**Brilliant Electric Sign Co., Ltd.**  
 4811 VAN EPPS RD., CLEVELAND, OHIO 44131 (216)741-3800

NOTE: THIS IS AN ORIGINAL UNPUBLISHED DRAWING. CREATED BY BRILLIANT SIGNS. IT IS THE PROPERTY OF BRILLIANT SIGNS. NO REPRODUCTION OR CONSTRUCTION WITH A PROJECT BEING PLANNED FOR YOU. IT IS NOT TO BE USED, REPRODUCED, COPIED OR EXHIBITED IN ANY FASHION.

COMPANY NAME	KeyBank		
LOCATION	85 Commercial Street, Portland, Maine		
SALESMAN	H	DATE	2-7-17
DESIGNER	DM	SCALE	1" = 1'-0"
REVISION		DESIGN NO.	B17-386
		COPYRIGHT ©	2017
		FILE NAME	I:/key 2017 CULS/85 commercial