



REVERSE FACE

**NOTES:**

Double-face, non-illuminated shingle-type sign, to suspend from illuminated support mast; sign to consist of 1/2" MDO sign panels with 3/8" PVC copy / logo, smalted backgrounds, and 1-1/2" x 3" rectangular tube top bar. 4" diameter cove molding, and copper drip cap, all mounted on 1" square tube frame. Copy to be painted white. Logo to be painted red PMS #1795C. Face backgrounds to be black sand smalted finish. Rectangular tube to be painted white. Edges of sign to be painted black.

NOTE: due to printer limitations, colors shown may not exactly match specified. Refer to material charts for true colors.



**Brilliant Electric Sign Co., Ltd.**

4811 VAN EPPS RD., CLEVELAND, OHIO 44131 (216)741-3800

COMPANY NAME	KeyBank		
LOCATION	85 Commercial Street, Portland, Maine		
SALESMAN	H	DATE	2-7-17
DESIGNER	DM	SCALE	1-1/2" = 1'-0"

REVISION	DESIGN NO.	B17-387
	COPYRIGHT ©	2017
	FILE NAME	1:/key 2017 CULS/85 commercial

NOTE: THIS IS AN ORIGINAL UNPUBLISHED DRAWING. CREATED BY BRILLIANT SIGNS. IT IS THE PROPERTY OF BRILLIANT SIGNS. NO REPRODUCTION OR TRANSMISSION IN ANY MANNER OR CONNECTION WITH A PROJECT BEING PLANNED FOR YOU, IT IS NOT TO BE USED, REPRODUCED, COPIED OR EXHIBITED IN ANY FASHION.