LIGHT FIXTURE SCHEDULE

TYPE	DESCRIPTION	SIZE	MANUFACTURER CAT. NO.	LENS/LOUVER	LAMPS	BALLASTS	VOLT.	NOTES
A	CEILING RECESSED DIRECT/INDIRECT	2 X 4	COOPER OVATION 2RD1-254T5RP-277EBT52	METAL PERFORATED	3-54W T5	1-1 LAMP 1-2 LAMP	277	ELECTRONIC T5 BALLASTS
B	SURFACE MOUNT PENDANT	55mm	BRUCK KANE UNI-LIGHT 220050MC	MATTCHROME WH GLASS	1-50W BI-PIN		277	NO SUB
C	TRACK MOUNTED CLOSE TO TRACK	3'	JUNO T5T32	BRUSHED S.S.	2-39W T5HO	ELECTRONIC	120	
D	CEILING SURFACE WRAPAROUND	4' L	COLUMBIA WCW4-232-EB8277	ACRYLIC PRISMATIC	2-32W T8	ELECTRONIC	277	
F	UNDERCOUNTER LIGHT	3' L	COLUMBIA UC36-125-EB8120-WSW	WHITE ACRYLIC	1-25W T8	ELECTRONIC	120	
G	CEILING RECESSED INTERIOR WALLWASH	6"	COOPER PORTFOLIO C6132-E-6110-LI-TRM6-P	OPEN	3-26W TRIPLE TUBE	ELECTRONIC	277	WALL WASH
H	CEILING RECESSED DOWNLIGHT	6"	COOPER PORTFOLIO C6132-E-6150-LI-TRM6-P	OPEN	3-26W TRIPLE TUBE	ELECTRONIC	277	
J	CEILING PENDANT MNTD DIRECT/INDIRECT FLUOR	8'	COOPER CORELITE AP-SP-2T5-2C-277-AC48-JB-8	-	4-54W T5	ELECTRONIC	277	MOUNT LIGHTS @ 8'6" AFF WITH CABLE
K	CEILING RECESSED ACRYLIC	2 X 4	LITHONIA 2SP F B 2 32 AI2 277 GEB	ACRYLIC PRISMATIC	2-32W T8	1	277	GYPSUM WALL BOARD CEILING
L	CEILING RECESSED ACRYLIC	2 X 4	LITHONIA 2SP G B 2 32 AI2 277 GEB	ACRYLIC PRISMATIC	2-32W T8	1	277	
M	CEILING PENDANT MNTD DIRECT/INDIRECT FLUOR	34"	SHAPER 494-34-CF8/26-277SSB-CC-XX"OA	WHITE ACRYLIC	8-F26TT	4 (MINIMUM) ELECTRONIC	277	MOUNT LIGHTS @ 15' AFF WITH PENDANT
M1	CEILING PENDANT MNTD DIRECT/INDIRECT FLUOR	22"	SHAPER 494-22-CF8/26-277SSB-CC-XX"OA	WHITE ACRYLIC	4-F26TT	2 ELECTRONIC	277	MOUNT LIGHTS @ 9' AFF WITH PENDANT
N	DIRECT/INDIRECT PARKING GARAGE	-	KIM PGL4-175MH277-DLN-L	POLYCARB	1-175W MH	1	277	NARROW DOWNLIGHT OPTICS
P	SURFACE STRIP LIGHT	4'	COLUMBIA CS4-232-EB8277	NONE	2-32W T8	ELECTRONIC	277	
Q	CEILING RECESSED DOWNLIGHT	6"	PRESCOLITE CFCB626QHEB	STCB6ACLSS	2-26W QUAD TUBE	ELECTRONIC	277	
S	WALL MOUNTED OVAL SCONCE	4" X 18"	SHAPER 693/4-S-CFI/26-277-CC-X	WHITE ACRYLIC	1-F26TT	ELECTRONIC	277	-
T	SURFACE MOUNTED OPEN/CLOSED SIGN	-	-	IMPACT REST POLYCARB	LED	-	277	OWNER SUPPLIED, ELECTRICAL CONTRACTOR TO INSTALL
U	TRACK MOUNTED DIRECT ACCENT	-	JUNO TFG116	T557 PRISMATIC	50W MR16	NONE	24	LIGHTS TO BE SPACED AROUND TRACK
V	FLEXABLE LOW VOLTAGE TRACK	TBD	JUNO FLEX 12 TRACK	NONE	-	STEPDOWN TRSFRM	120	TRACK TO BE BENT TO MATCH WOOD CEILING
W	SINLE CIRCUIT TRACK	VARIES	JUNO TRACKMASTER	NONE	-	-	120	TRACK TO BE MOUNTED BETWEEN WOOD LATS

WBRC
ARCHITECTS • ENGINEERS
44 Central Street
Bangor, Maine 04401
tel (207) 947-4511
fax (207) 947-4628

PROJECT:

BSB
FORE STREET

SUBJECT:

LIGHT FIXTURE
REVISIONS

SCALE: 1/4" = 1'-0"

WBRC CAD FILE: 2747-69-E-001

PROJECT No. 2747.69

JOB CAP/DRAW: PEB

PM: MLC

CHECKED BY: RLR

DATE: 06-25-2004

SHEET No.

ADD1-E-001-1

© COPYRIGHT 2004 WBRC