

•
•
•
•
•
•
•

389 Congress St.Rm 315
Portland, ME 04101
Phone: (207)874-8700
Fax: (207)874-8716

facsimile transmittal

To: Judy Johnson/SMRT **From:** Mike Nugent

Fax: 772-1070 **Date:** July 31, 2002

Phone: 774-3846 **Pages:** 1

Re: Hilton Garden Inn (029 K003) **CC:**

Urgent For Review Please Comment Please Reply Please Recycle



Notes:

I'm finishing the review of the plans for the above and have a couple of questions:

- 1) What is the fire resistance rating of the floor/ceiling assembly between the Assembly Use and the R1 use, as well as the other floors?
- 2) Detail A4 on page AE412 shows a 4" space between the lower rail of the guard and the stair assembly, this needs to be "less than 4 inches" (picky I know)
- 3) Please direct me to the detail that shows the fire separation assemblies for the penetrations in the floor systems for plumbing, HVAC and electrical.
- 4) What is the fire resistance rating of the floor/ceiling assembly between the area where automobiles park for registration and the R1 use?
- 5) Will need additional permits for fire alarm, plumbing, electrical, heating and fire suppressions systems
- 6) Please forward the Statement of Special Inspections (1705 Of the Building Code)

