<u>LIGHTING NOTES:</u>

- I. ELECTRICAL WORK SHALL CONFORM TO ALL LOCAL, STATE, AND FEDERAL STANDARDS, CODES, AND GUIDELINES.

 2. SIGNIFICANT DESIGN ALTERATIONS, ADDITIONS, OR DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN
- PROFESSIONAL BEFORE PROCEEDING.

 3. THE ELECTRICAL CONTRACTOR IS RESPONSIBLE FOR COORDINATING THE ELECTRICAL SYSTEM INSTALLATION WITH ALL TRADEG INCLUDING MECHANICAL ARCHITECTURAL CITIZENAL AND PLUMPING.
- TRADES INCLUDING MECHANICAL, ARCHITECTURAL, STRUCTURAL, AND PLUMBING.

 4. THE ELECTRICAL CONTRACTOR IS RESPONSIBLE FOR VERIFYING THAT SERVICE SIZE IS ADEQUATE.
- 5. ALL PENETRATIONS THROUGH FIRE-RESISTANT RATED WALL, FLOOR/CEILING AND ROOF/CEILING ASSEMBLIES SHALL BE MADE IN ACCORDANCE WITH AN APPROVED U.L. LISTED THRU-PENETRATION ASSEMBLY AND SUCH ASSEMBLY IS THE RESPONSIBILITY OF THE ELECTRICAL CONTRACTOR.

 6. EXTERIOR LIGHTING TO BE PROVIDED WITH A PHOTOCELL AND TIMER.
- 6. EXTERIOR LIGHTING TO BE PROVIDED WITH A PHOTOCELL AND TIMER.

 7. EXTERIOR POLE MOUNTED FIXTURES TO BE AS INDICATED ON THE SITE PLAN. SITE LIGHTING TO INCLUDE WALKWAY
- BOLLARDS AND POLE LIGHTS.
- 8. ALL EXPOSED WIRING SYSTEMS ARE TO BE RUN IN E.M.T. OR RIGID CONDUITS RUN TIGHT TO THE FLOOR DECK OR CONTINUOUSLY ALONG OTHER STRUCTURAL COMPONENTS.

 9. COLOR FOR ELECTRICAL COVER PLATES AND COMPONENTS TO MATCH THE BUILDING COLOR SCHEME.
- IO. CENTER FIXTURES IN CEILING TILES.

 II. ELECTRICAL CONTRACTOR IS RESPONSIBLE FOR SUPPLYING CONDUITS TO THE BUILDING FOR TELEPHONE FIBER OPTIC AND
 CABLE SERVICES.
- 12. FLOOR/CEILING ASSEMBLIES ARE 2 HR. FIRE-RATED. ROOF/CEILING ASSEMBLIES ARE I HR. FIRE-RATED.
 13. ELECTRICAL CONTRACTOR TO PROVIDE FIXTURE SUBMITTALS AND CIRCUITED DRAWING, INCLUDING PANEL DIAGRAMS FOR APPROVAL PRIOR TO INSTALLATION.
- APPROVAL PRIOR TO INSTALLATION.
 14. CEILINGS DO NOT SERVE AS RETURN AIR PLENUM.
 15. UPLIGHTING SHALL BE INSTALLED AROUND THE PERIMETER OF THE BUILDING. LOCATION OF LIGHTS SHALL BE COORDINATED
- WITH THE MASONRY CONTRACTOR. THE UPLIGHTS MUST BE CONTROLLED BY A PHOTOELECTRIC CELL. PROVIDE MIN. 1/2" RIGID CONDUIT TO EACH FIXTURE. THE CONTROL SYSTEM MUST SWITCH ALL LIGHTS ON AND OFF SIMULTANEOUSLY.

 16. MINIMUM LIGHTING LEVEL UNDER CANOPY MUST BE TEN FOOT-CANDLES.
- 17. MINIMUM LIGHTING LEVEL MUST BE TEN FOOT-CANDLES IN THE LOBBY AND 30 FOOT-CANDLES AT THE REGISTRATION DESK SURFACE. 18. FIFTY FOOT-CANDLES OF ILLUMINATION MUST BE PROVIDED AT COUNTER HEIGHT AT BREAKFAST/PANTRY AREA. ALL
- LIGHTING WITHIN THE BREAKFAST SERVING AREA MUST BE DIMMABLE.

 19. PROVIDE A MINIMUM OF SIXTY FOOT-CANDLES OF GENERAL LIGHTING MEASURED AT DESK HEIGHT AT THE BUSINESS CENTER.

 LIGHTS MUST BE WIRED TO REMAIN ON AT ALL TIMES.
- 20. LIGHT LEVEL AT THE MEETING ROOM TABLETOPS MUST BE A MINIMUM OF 50 FOOT-CANDLES. PROVIDE LIGHTING ON DIMMER SMITCHES.
 21. PROVIDE ONE UNDERWATER LIGHT IN THE POOL MINIMUM. THE CIRCUITS SUPPLYING THE UNDERWATER LIGHTING FIXTURES MUST
- BE LOW VOLTAGE AND MUST BE PROTECTED THROUGH AN APPROVED GROUND FAULT INTERRUPTER. POOL LIGHT SHALL REMAIN ACTIVE DURING OFF HOURS.

 22. PROVIDE FIVE FOOT-CANDLES MINIMUM MEASURED AT THE DECK SURFACE. LIGHTS SHALL BE KEY SWITCHED.

 23. ELECTRICAL DISTRIBUTION MUST BE MADE SUCH THAT INDIVIDUAL CIRCUIT PROBLEMS IN ONE GUEST ROOM DO NOT AFFECT
- 23. ELECTRICAL DISTRIBUTION MUST BE MADE SUCH THAT INDIVIDUAL CIRCUIT PROBLEMS IN ONE GUEST ROOM DO NOT AFFECT ANY OTHER GUEST EXPERIENCE. PROVIDE AT LEAST THREE 20-AMP CIRCUITS FOR GENERAL LIGHTING AND RECEPTACLE REQUIREMENTS, WITH A SEPARATE GFCI CIRCUIT FOR THE BATH.
- 24. LIGHTING WITH A LEVEL OF 10 FOOT-CANDLES MINIMUM, MEASURED AT FLOOR LEVEL, MUST BE PROVIDED IN CORRIDORS, AND 15 FOOT-CANDLES MINIMUM AT THE ENTRY DOOR LOCK.
- 25. AN EMERGENCY BACKUP GAS GENERATOR SHALL BE PROVIDE TO RUN ALL PUBLIC LIGHTING, ELEVATOR AND ALL OTHER EMERGENCY CIRCUITS AS REQUIRED BY CODE.

LIGHTING SCHEDULE				
TYPE	MANUFACTURER	CATALOGUE #	DESCRIPTION	
A	LITHONIA	SB 2 32 MV <i>O</i> LT	WRAPAROUND	
3	LITHONIA	2GT72U3I6AI2MVOLT	2x2 RECESSED	
5	LITHONIA	AFI/32TRT6ARMVOLT	NON DIM DOWN	
D	LITHONIA	AFI/32TRTDIM6ARMVOLT	DIM DOWN	
M	LITHONIA	AFWI/32TRTDIM6ARMVOLT	DIM WALL WASH	
)	GEORGE KOVACS	PSIII0-617	VANITY LIGHT	
•	PROGRESS	P6140-09A	PENDANT	
	PROGRESS	P6125-09	TRACK HEAD	
=	PROGRESS	P6140	TRACK PENDANT HEAD	
,	PROGRESS	P9200-28	TRACK HEAD	
+	LIGHTOLIER	C4X42OLEDDL27KCCL/C4X42OLEDI	5" SQUARE RECESSED LED	
j	LIGHTOLIER	C4X42OLEDWW27KCCLW/C42OLEDI	5" RECESSED LED WALL WASHER	
<	LIGHTOLIER	C4X420LEDWW27KCCZP/C420LEDI	5" RECESSED LED WALL WASHER	
-	LIGHTOLIER	PRA2GREVA23227750	2X4 RECESSED LENS TROFFER	
- 4	MINONA LIGHTING	P2-55-MH70-277V-5KI-5GW-PG-5TD	SMALL WALL MOUNT HID	
, 1	MINONA LIGHTING	P3-SSW-MHI50-277V-SKI-SPF-PG-STD	SMALL WALL MOUNT HID OUTDOOR LOCATION	
	VATOR ACCESSORIES	P5-55N-MH150-211V-5N1-5PF-P6-51D APL-1	ELEVATOR PIT LIGHT	
) 기	TBD	TBD	DECORATIVE FIXTURE	
2	TBD		DECORATIVE FIXTURE	
r2 P3	TBD	TBD	DECORATIVE FIXTURE	
P4	TBD	TBD	DECORATIVE FIXTURE	
a Q	LIGHTOLIER	TBD		
х ?		408320	ADA COMPLIANT WALL SCONCE	
5	TRINITY LIGHTING	59589-HBRZ-24-LT-801	24" DECORATIVE FLUORESCENT WALL MOUNTED	
5 T	TRINITY LIGHTING	59589-HBRZ-36-LT-800	36" DECORATIVE FLUORESCENT WALL MOUNTED	
	TRINITY LIGHTING	50533-FL-PTBZ-LT-700	SURFACE/CEILING MOUNTED (2) PLIBM FLUORESCENT	
J	TRINITY LIGHTING	5051A-BNICK-LT-900	PENDANT FOR SUITE DIVIDER	
Y	TBD	TBD	RECESSED DOWNLIGHT	
N.	TBD	TBD	RECESSED DOWNLIGHT	
X	LIGHTOLIER	C6LI52ODL	6" ROUND RECESSED DOWNLIGHT LED	
<u> </u>	LIGHTOLIER	C4LIODL	4" ROUND RECESSED DOWNLIGHT LED	
Z .	TBD	TBD	SURFACE MOUNTED DECORATIVE FIXTURE	
44	TBD	TBD	RECESSED FLUORESCENT DOWNLIGHT	
3B	TBD	TBD	MINI-PENDANT HALOGEN LIGHT W/ TILLIA SHADE	
	TBD	TBD	SURFACE MOUNTED FLUORESCENT LIGHT	
DD 	PANAMEX GROUP	AZ70RVL	RECESSED FAN/LIGHT 2.0 SONES MAX.	
E	TBD	TBD	DECORATIVE SURFACE MOUNT VANITY FIXTURE	
FF	TBD	TBD	SURFACE MOUNT DECORATIVE FIXTURE	
<i>36</i>	B-K LIGHTING	DS-LED-e23-NSP-12	DELTA STAR - N SPOT	
HH	LURALINE	HL30IXLWM-SE-BL-M50/R	DECORATIVE WALL MOUNT	
IJ	LUMENTON	W2D27I-MHC220-RMT-B	7" ROUND 2 DIRECTIONAL, WALL LUMINAIRE (2 LAMP	

LIGHTING LEGEND			
SYMBOL	DESCRIPTION		
¤	RECESSED DOWNLIGHT		
	FLUORESCENT STRIP LIGHT		
	2'x2' RECESSED FLUORESCENT LIGHT WITH PRISMATIC LENS		
	2'x4' RECESSED FLUORESCENT LIGHT WITH PRISMATIC LENS		
×	PENDANT FIXTURE		
Ħ	WALL WASHER RECESSED FIXTURE		
\diamond	SURFACE MOUNTED FIXTURE		
Q	WALL MOUNTED FIXTURE		
\sim	FLEXIBLE SUSPENDED LIGHT TRACK		
<u> </u>	TRACK MOUNTED FIXTURE		
Ψ			
$\nabla \nabla \nabla$	STRAIGHT LIGHT TRACK		
0	SQUARE RECESSED DOWNLIGHT		
©	DECORATIVE LIGHT FIXTURES		
₩ 5000	DESCRIPT FIXTURES		
PC	PHOTOCELL (MOUNTING LOCATION T.B.D.)		
	PHOTOCELL (MOUNTING LOCATION 1.B.D.)		
\$	SINGLE-POLE SMITCH MOUNTED 42" A.F.F. TO CENTER		
\$ ₃	THREE-WAY SMITCH MOUNTED 42" A.F.F. TO CENTER		
_	SINGLE-POLE SWITCH WITH MOTION/INFRARED SENSOR		
\$ M	MOUNTED 42" A.F.F. TO CENTER		
$*_{\mathcal{D}}$	DIMMER SMITCH MOUNTED 42" A.F.F. TO CENTER		
	 "IN-USE" INDICATOR LIGHT		
\$ ₁			
\$ _K	KEYED SMITCH		

CONSTRUCTION CORPORATION
11 CORPORATE DRIVE, BELMONT NH 03220
PHONE (603) 527-9090 FAX (603)527-9191

LIGHT LEGENDS AND NOTES

Hotel, Restaurant,

Portside Residences

DATE: 08-24-10
SCALE: As Shown
DRAWN BY: dwb