



PIPE TO RUN HORIZONTALLY IN WALL TO AVOID STRUCTURAL MEMBERS TO VERTICAL RISER IN CHASE. DO NOT EXCEED MAX. DISTANCE FROM TRAP AS ALLOWED BY CODE (TYP.)

PROVIDE WASTE AND VENT STACKS FOR INDIVIDUAL GUESTROOMS. CONCEAL IN WALLS OR SHAFTS. INSTALLATION TO MEET UL LISTED THROUGH-PENETRATION FIRESTOP SYSTEM FOR MATERIAL USED (TYP.)

ACCESS PANEL THROUGH GUESTROOM CLOSET (TYP.)
 PROVIDE CONDENSATE RISER FOR ALL GUESTROOM HVAC UNITS (TYP.)

BATH WASTE AND OVERFLOW UNITS

VERTICAL WASTE STACK IN SHAFT. COORDINATE WITH BATHROOM EXHAUST VENT DUCT (TYP.)

DATE	REVISION SCHEDULE	REVISION DESCRIPTION	BY

LOPECHEE
 CONSTRUCTION CORPORATION
 11 CORPORATE DRIVE, BELMONT, NH 03220
 PHONE (603) 271-9090 FAX (603) 271-9191

**FOURTH FLOOR
 PLUMBING PLAN**

PROJECT: **Hotel, Restaurant,
 & Portside Residences** Portland ME

DATE: 06-15-10
 SCALE: 1/8"=1'-0"
 DRAWN BY: dwb

SHEET: **P4**

