Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 11/21/14

1 EXISTING CONDITIONS AND DEMO PLAN
Scale: 1/4" = 1'-0"

DEMOLITION NOTES

1. Demolish and remove walls, doors, and windows
2. Demolish and remove existing ACT, dropped ceiling or other to the existing pressed tin ceiling
3. Demolish and remove elevated floor systems
4. Demolish and remove plumbing fixtures
5. Demolish and remove existing finished floorng down to sub-floor
6. Demolish existing ACT and replace with new ACT after hood and new equipment installation.
7. Remove existing door and frame.
8. Remove existing door and frame, prep for infill.
9. Remove existing EXIT SIGN over door.

PERMIT SET

STATE OF MAINE
SHAWN CHRISTOPHER DOLLEY
3112
REGISTERED ARCHITECT

Design Firm
RESIDENTIAL DESIGN STUDIO, LLC
Carol A. Morrissette
174 Danforth Street
Portland, Maine 04102
T 207.699.4184 C 207.671.7965

Revisions
1
2
3

Project Title
80-90 Middle Street - AMA
Portland, Maine
B3 ZONE CBL 29 L4-1

Sheet Title
DEMO PLAN

Sheet Status: Pre-Application
Project Number: 13.70
Date: July 30, 2014
Drawn By: MBC
Sheet No.: D1.1
Sheet Scale: 1/4"=1'-0"
CAD File Number: 80-90_Middle_Street_AMA-Permit set.dwg